

FULL ADDRESS:
100 GLENBOROUGH, SUITE 100
HOUSTON, TX 77067-3610

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
B. TYPE OF WELL: OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>		7. UNIT or CA AGREEMENT NAME: N/A
2. NAME OF OPERATOR: NOBLE ENERGY, INC.		8. WELL NAME and NUMBER: ANTELOPE HOLLOW STATE* 32-20
3. ADDRESS OF OPERATOR: 100 GLENBOROUGH CITY HOUSTON STATE TX ZIP 77067-3610		9. FIELD AND POOL, OR WILDCAT: WILDCAT
PHONE NUMBER: (281) 872-2506		10. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1844 FNL & 2046 FEL 600440 X 40.982639 AT PROPOSED PRODUCING ZONE: SAME 4537304Y - 109.806090		11. COUNTY: DAGGETT
13. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 5 AIR MILES WEST OF MANILA		12. STATE: UTAH
14. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 524'	15. NUMBER OF ACRES IN LEASE: 1,738	16. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40
17. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) N/A	18. PROPOSED DEPTH: 18,500	19. BOND DESCRIPTION: 6313458 (BLANKET \$120,000)
20. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 7,093' GL	21. APPROXIMATE DATE WORK WILL START: 12/21/2004	22. ESTIMATED DURATION: 16 WEEKS

23. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
24	20	CON-	DUCTOR	100	PREMIUM LITE II	63 SX	2.27 12.0
17-1/2	13-3/8	J-55	61	2,000	PREMIUM LITE II	910 SX	2.27 12.0
17-1/2	13-3/8	J-55	61	2,000	CLASS G	805 SX	1.17 15.8
12-1/4	9-5/8	P/S	47	10,000	PREMIUM LITE II	810 383 SX	2.25 3.15 11.0 12.0
12-1/4	9-5/8	P/S	47	10,000	CLASS G	382 SX	1.15 15.8
8-1/2	5-1/2	P-110	23	18,500	PREMIUM LITE II	810 SX	1.90 13.0
8-1/2	5-1/2	P-110	23	18,500	CLASS G	650 SX	1.56 15.6

*FULL WELL NAME & NUMBER:

24. ATTACHMENTS ANTELOPE HOLLOW STATE 32-20


VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- | | |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) BRIAN WOOD PHONE: (505) 466-8120 TITLE CONSULTANT FAX: (505) 466-9682
SIGNATURE Brian Wood DATE 12/3/2004

(This space for State use only)



API NUMBER ASSIGNED: 43-009-30065



RECEIVED
DEC 06 2004

DIV. OF OIL, GAS & MINING

R. 19 E.




T. 3 N.

LATITUDE
NORTH 40.982654 DEG.
LONGITUDE
WEST 109.806055 DEG.

NORTHING
116879.95

EASTING
208423.92

BASIS OF BEARING & DATUM
SPCS WYWC NAD 27 BASED
GPS POSITION
CORS CORRECTED




SURVEYOR'S STATEMENT

I, Brian L. Forbes, of Rock Springs, Wyoming, hereby state: This map was made from notes taken during an actual survey under my direct supervision on NOVEMBER 17, 2004, and it correctly shows the location of ANTELOPE HOLLOW STATE 32-20.

NOTES

- ◆ WELL LOCATION
- FOUND MONUMENT
- L DENOTES 90° TIE
- CALCULATED CORNER

EXHIBIT 1



RIFFIN & ASSOCIATES, INC.
1414 ELK ST., ROCK SPRINGS, WY 82901

**PLAT OF DRILLING LOCATION
FOR
NOBLE ENERGY, INC.**

**1844' F/NL & 2046' F/EL, SECTION 20,
T. 3 N., R. 19 E., SALT LAKE P.M.
DAGGETT COUNTY, UTAH**

PH. (307) 362-5028

SCALE: 1" = 1000'

FAX (307) 362-1056

JOB No. 11910

DATE DRAWN: 11/29/04

Noble Energy, Inc.
 Antelope Hollow State 32-20
 1844' FNL & 2046' FEL
 Sec. 20, T. 3 N., R. 19 E.
 Daggett County, Utah

Drilling Program

1. ESTIMATED FORMATION TOPS

<u>Formation Name</u>	<u>GL Depth</u>	<u>KB Depth</u>	<u>Elevation</u>
Bridger (ground level)	0'	30'	+7,093'
Green River	263'	293'	+6,830'
Wasatch	2,863'	2,893'	+4,230'
Fort Union	5,863'	5,893'	+1,230'
Almond	10,063'	10,093'	-2,970'
Mesa Verde	10,263'	10,293'	-3,170'
Ericson	10,654'	10,684'	-3,561'
Rock Springs	11,462'	11,492'	-4,369'
Blair	12,696'	12,726'	-5,603'
Mancos Hilliard	13,185'	13,215'	-6,092'
Niobrara	14,039'	14,069'	-6,946'
Base Niobrara	14,589'	14,619'	-7,496'
Frontier	17,442'	17,472'	-10,349'
Mowry	17,594'	17,624'	-10,501'
Dakota	17,790'	17,820'	-10,697'
Lower Dakota	17,852'	17,882'	-10,759'
Morrison	18,078'	18,108'	-10,985'
Total Depth (TD)	18,500'	18,530'	-11,407'

2. NOTABLE ZONES

Primary goal is the Dakota. Secondary goals are the shallower Cretaceous zones.

Oil & Gas Zones

Almond
 Ericson

Water Zones

Bridger
 Fort Union

Coal Zone

Fort Union

Noble Energy, Inc.
Antelope Hollow State 32-20
1844' FNL & 2046' FEL
Sec. 20, T. 3 N., R. 19 E.
Daggett County, Utah

PAGE 2

Oil & Gas Zones

Rock Springs
Mancos Hilliard
Frontier
Dakota

3. PRESSURE CONTROL SYSTEM (See PAGES 3 & 4)

A 5,000 psi double ram, annular preventer, choke manifold, and kill line of the same rating will be used from surface casing to $\approx 10,000'$. Will test to 5,000 psi high and 250 psi low. Test Hydril® to 2,500 psi.

A 10,000 psi system will be used from $\approx 10,000'$ to TD. Typical BOP stack, choke, and kill line models follow. Drilling contract has not yet been awarded, thus the exact system to be used is not known now.

Hydraulic controls will be on the rig floor and at the accumulator. The latter will be 100' from the well bore and next to the light plant. Auxiliary equipment will include upper and lower kelly cock valves with handles available, drill pipe safety valve on the floor to fit all strings in use, inside BOP or float sub available, and electronic pit volume monitor. All BOP connections will be flanged, welded, or clamped. Kill line will run unobstructed to the far edge of the substructure.

Stack and choke manifold will be tested when installed and at least once every 30 days thereafter. Tests to 0.22 psi/ft. or 1,000 psi, whichever is more, will be conducted before drilling out all cemented in place casing strings. BOP controls will be installed before drilling the surface casing plug, and will stay in use until the well is completed or plugged and abandoned. Pipe rams will be tested daily. Blind rams will be tested on all trips.

Noble Energy, Inc.
Antelope Hollow State 32-20
1844' FNL & 2046' FEL
Sec. 20, T. 3 N., R. 19 E.
Daggett County, Utah

PAGE 5

Manual control equipped ram preventers will be tested to the rated working pressure of the stack or to 70% of the internal yield of the casing, whichever is less. Ram preventers will be tested to working pressure if a test plug is used. Annular preventer will be tested to 50% of its rated working pressure. BOPs will be inspected and operated at least daily to assure good mechanical working order. All BOP mechanical tests, pressure tests, and inspections will be recorded on the driller's log or the daily drilling report.

4. CASING & CEMENT

<u>Hole Size</u>	<u>O. D.</u>	<u>Pounds/Foot</u>	<u>Grade</u>	<u>Type</u>	<u>Age</u>	<u>Interval</u>
24"	20"		Conductor Pipe		New	0' - 100'
17-1/2"	13-3/8"	61	J-55	B T & C	New	0' - 2,000'
12-1/4"	9-5/8"	47	P/S	L T & C	New	0' - 10,000'
8-1/2"	5-1/2"	23	P-110	L T & C	New	0' - 18,500'

Conductor pipe will be cemented to surface with ≈ 144 cubic feet (50% excess).

Surface casing will be cemented to the surface with $>100\%$ excess. Float collar will be set at $\approx 1,920'$.

Lead slurry will be ≈ 910 sacks ($\approx 2,066$ cubic feet) Premium Lite. II + 2% CaCl_2 + 1/4 pound per sack cello flake + 8% bentonite + 124.4% fresh water. Density = 12.0 pounds per gallon. Yield = 2.27 cubic feet per sack.

Tail slurry will be ≈ 655 sacks (≈ 766 cubic feet) Class G + 2% CaCl_2 + 1/4 pound per sack cello flake + 44.3% fresh water. Density = 15.8 pounds per gallon. Yield = 1.17 cubic feet per sack.

Top out slurry will be ≈ 150 sacks (≈ 174 cubic feet) Class G + 2% CaCl_2 + 44.4% fresh water. Density = 15.8 pounds per gallon. Yield = 1.16 cubic feet per sack.

Clinton Dworshak - Antelope Hollow State 32-20 / Intermediate Casing Cement Job

From: <MStringfield@nobleenergyinc.com>
To: <clintondworshak@utah.gov>
Date: 12/27/2004 4:01 PM
Subject: Antelope Hollow State 32-20 / Intermediate Casing Cement Job
CC: <BMurphy@nobleenergyinc.com>

Clint - We will alter our drill procedure to bring the top of cement for the intermediate casing up to 2800' to cover the Wasatch. To do this we will retain the tail slurry design included in the APD but will change the lead slurry density to 11.0 ppg which will give it a yield of 3.15 cf/sk. To achieve 6200' of fill (9000' up to 2800') with 30% excess will require 2524 cf of slurry which is 810 sks.

Thanks for helping us get this APD approved. If I can provide any further information please call (281-874-6780). Mark

Noble Energy, Inc.
Antelope Hollow State 32-20
1844' FNL & 2046' FEL
Sec. 20, T. 3 N., R. 19 E.
Daggett County, Utah

PAGE 6

Intermediate casing will be cemented to $\approx 7,000'$ with $>33\%$ excess. Float collar will be set at $\approx 9,920'$.

810

Lead slurry will be ≈ 363 sacks (≈ 817 cubic feet) Premium Lite II + 0.02 pounds per sack Static Free + 0.65% R-3 low temperature retarder + 8% bentonite.

Density = $\frac{11.0}{12.0}$ pounds per gallon. Yield = $\frac{3.15}{2.25}$ cubic feet per sack. *amended by email 12/27/04 from Mark Stringfield*

Tail slurry will be ≈ 382 sacks (≈ 439 cubic feet) Class G + 0.3% R-3 + 0.2% CD-32 polymer dispersant + 1% FL-25 fluid loss control additive + 0.05 gps FP-6L foam control. Density = 15.8 pounds per gallon. Yield = 1.15 cubic feet/sack.

There will be $\approx 500'$ of overlap between top of long string cement and bottom of intermediate string cement. Production casing will be cemented to $\approx 9,500'$ with $>20\%$ excess. Float collar will beset at $\approx 18,420'$.

Lead slurry will be ≈ 810 sacks Premium Lite II High Strength + 0.4% R-3 + 0.5% CD-32 + 0.6% FL-52 fluid loss additive + 0.3% sodium metasilicate. Density = 13.0 pounds per gallon. Yield = 1.90 cubic feet per sack.

Tail slurry will be ≈ 650 sacks Class G cement + 35% silica flour fluid loss control + 0.3% R-3 + 0.2% CD-32 + 1% FL-25 + 0.05 gps FP-6L. Density = 15.6 pounds per gallon. Yield = 1.56 cubic feet per sack.

5. MUD PROGRAM

<u>Depth</u>	<u>Base</u>	<u>ppg</u>	<u>Viscosity</u>	<u>YP</u>	<u>LGS</u>
0' - 2,000'	Fresh water gel	8.6 - 8.9	30 - 50	8 - 10	$<6\%$
2,000' - 10,000'	Fresh water polymer	8.6 - 8.9	34 - 42	12 - 15	$\leq 100\%$
10,000' - TD	Oil base	9.0 - 12.0	40 - 55	8 - 15	≤ 60 ppb

Drill surface hole with fresh water, soda ash to treat hardness, 0.1 ppb EZ mud, + 15 ppb Aqua Gel. Dump/dilute for solids and add Crystal Drill to flocculate reserve pit. Use SAPP for bit balls. Use Maxiseal for lost circulation.

Noble Energy, Inc.
Antelope Hollow State 32-20
1844' FNL & 2046' FEL
Sec. 20, T. 3 N., R. 19 E.
Daggett County, Utah

PAGE 7

Intermediate hole will be drilled with fresh water polymer. Use 4 ppb Aqua Gel for wall cake and filtration control. Mud up with 0.5 ppb EZ Mud in fresh water and add 0.25 ppb Barazan-D for yield point. Add 0.25 - 0.5 ppb PAC-R for filtration. Add Aldacide-G for biocide. Use Fiber-Plug, Micatex, and sawdust to control lost circulation. Add caustic soda to prevent drill pipe corrosion.

Long string hole will be drilled with oil based mud due to low friction coefficient, longer bit life, lower mud weight, less chance of stuck pipe, smaller reserve pit, stabilizes shale, keeps well bore near gauge, longer life, and faster drilling. Displace hole with Invermul RF oil base mud. Use Geltone V for viscosity/yield point. Use EZ Mul/Invermul for emulsion. Maintain 4 ppb excess lime. Use Barablok to control HTHP. Use liquid sack CaCl_2 for water phase salinity. Raise weight only if needed to control gas.

Mud logger will be on location from base of surface casing to TD.

6. CORES, TESTS, & LOGS

Rotary side wall cores may be cut after evaluating logs. Drill stem tests may be run in the target zones if good shows are found. Induction, dipole sonic, density, neutron CMR logs will be run from base of surface casing to TD. Deviation surveys will be run every $\approx 500'$

7. DOWN HOLE CONDITIONS

No hydrogen sulfide is expected. Maximum bottom hole temperature = 253°F . Maximum bottom hole pressure should be $\approx 9,100 \text{ psi}$.

8. OTHER INFORMATION

The anticipated spud date is December 21, 2005.

Noble Energy, Inc.
Antelope Hollow State 32-20
1844' FNL & 2046' FEL
Sec. 20, T. 3 N., R. 19 E.
Daggett County, Utah

PAGE 8

Surface Use Plan

1. DIRECTIONS & EXISTING ROADS (See PAGES 13 & 14)

From the junction of U-43 and U-44 in Manila, Utah
Go West 5.1 miles on U-43 to a wire gate (equivalent to Mile Post 2.8)
Then turn right and go North 0.15 mile along West side of fence
Then turn right and go East 0.35 miles to proposed well

2. NEW ROAD (See PAGE 14)

The last 0.5 mile of road will be built. It will have a $\geq 16'$ wide running surface and be crowned and ditched. Maximum disturbed width = 50'.

Existing gap in fence will be widened to 50' and an 18" x 50' culvert installed in the borrow ditch. A 20' wide cattle guard and gate will be installed $\approx 60'$ north of the pavement. That portion of the road south of the cattle guard will be surfaced with a base of $\approx 6"$ of pit run topped with $\approx 3"$ of gravel. The north-south fence will be shifted east and a new gate installed.

Road will then be built north ≈ 0.15 mile from the cattle guard along the west side of the fence. Then it will then go east ≈ 0.35 mile to the proposed pad. A cattle guard will be installed in the second fence. Culverts will be installed in the irrigation ditches and road as directed by the surface owner.

3. EXISTING WELLS (See PAGE 14)

There is one P & A well and six water wells within a mile radius. There are no gas, oil, injection, or disposal wells within a mile. Closest water well is 2,597' southwest.

Noble Energy, Inc.
Antelope Hollow State 32-20
1844' FNL & 2046' FEL
Sec. 20, T. 3 N., R. 19 E.
Daggett County, Utah

PAGE 9

4. PROPOSED PRODUCTION FACILITIES

A tank battery, dehydrator, meter run, and separator or heater-treater will be installed on the cut portion of the pad. All will be painted a flat earth tone color. Dikes of impervious compacted soil will surround all production vessels. Dikes will hold $\geq 110\%$ of the capacity of the largest tank. Load lines will end with a barrel beneath the end to catch drips.

5. WATER SUPPLY

Water will be (depending on weather) piped via a temporary surface pipeline or trucked from the surface owner's water wells. The wells are in SW4 Section 17 (#41-451), SE4 Section 19 (#41-3160 & #41-3209), or SW4 Section 20 (#41-3159).

6. CONSTRUCTION

Blue Stakes Location Center (1-800-662-4111 or 801-532-5000) will be called at least two full business days before construction starts. Entire well site will be fenced before construction starts. A gate and/or cattle guard will be installed at the entrance to the pad. At least top 6" of topsoil will be stripped and piled west of the pad. Pit subsoil will be piled south of the pad. A diversion ditch will be cut south of the subsoil pile and inside the fence. Ditch will be at least 425' long. Reserve pits will be lined with 1 x 10⁻⁷ cm/sec reinforced ultraviolet and hydrocarbon resistant liner. Liner top will be buried.

7. WASTE DISPOSAL

Portable, self-contained chemical toilets will be provided for human waste disposal. Upon completion of operations, and as needed, toilet tanks will be

Noble Energy, Inc.
Antelope Hollow State 32-20
1844' FNL & 2046' FEL
Sec. 20, T. 3 N., R. 19 E.
Daggett County, Utah

PAGE 10

pumped and the contents disposed of in an approved sewage disposal facility. Disposal will comply with state rules and regulations.

Trash and other solid waste (including cans, paper, cable, etc.) will be contained in portable trash cages. Trash cage contents will be disposed of in a state approved sanitary landfill as needed and upon completion of operations.

The reserve pits will not be used for flaring or trash disposal. All flaring will be directed to a separate flare pit or temporary flare stack. Discharge point will be ≥ 120 feet away from the well bore, line securely anchored, and flared down wind. Frac fluid or load water may be discharged to the reserve pit as long as its materials are RCRA exempt, at least two feet of freeboard is maintained, and the fluids are chemically compatible with the pit liner.

Drill cuttings and drilling fluids (including salts and chemicals) will be disposed of in the reserve pit. The reserve pit will be designed to prevent the collection of surface runoff. Liquid hydrocarbons produced during completion operations will be placed in test tanks on the well location.

Any spills of oil or any other potentially hazardous material will be cleaned up and immediately removed to an approved disposal site.

8. ANCILLARY FACILITIES

There will be no air strips or camps. Camper trailers will be on the pad for the company man, tool pusher, and mud logger.

9. WELL SITE LAYOUT

See PAGES 15 -17 for depiction of the well pad, existing facilities, reserve pit, trash cage, access onto the pad, parking, living facilities, and rig orientation.

Noble Energy, Inc.
Antelope Hollow State 32-20
1844' FNL & 2046' FEL
Sec. 20, T. 3 N., R. 19 E.
Daggett County, Utah

PAGE 11

10. RECLAMATION

Rat and mouse holes will be filled and compacted as soon as the rig is removed.

Floating hydrocarbons will be removed from the pits as soon as possible after drilling operations cease. If this is not practical, the pit containing the oil or other adverse substance will be flagged overhead or covered with wire or plastic mesh to deter birds. Drill cuttings and mud will remain in the reserve pits until dry. Solibond® will be used to stabilize any pit with oil base mud as discussed with Gil Hunt. The pits will not be squeezed, crowded, or cut. When back filled, pit contents will be covered with at least 3' of dirt.

Reclamation starts once the reserve pits are dry, at which point they will be back filled. The pad and filled pits will be contoured to a natural shape and disturbed areas ripped or harrowed. A seed mix to be determined by the surface owner will be sown how and when to be determined by the surface owner. If the well is a producer, then the reserve pits and any other areas not needed for work overs will be reclaimed as previously described.

11. SURFACE OWNER

All construction is on surface owned by the Circle Bar Ranch. Ranch owner is George Olson. his address is Circle Bar Ranch Road, Manila, UT 84046. His phone numbers are (435) 784-3200 and (435) 784-3500. A surface use agreement affidavit is attached.

12. OTHER INFORMATION

Nearest hospitals are ≈70 miles away in Rock Springs (Memorial Hospital at 1200 College Drive (307) 362-3711)) or Vernal (Ashley Valley Medical Center at 151 West 200 North (435) 789-3342)). Rock Springs is a faster drive.

Noble Energy, Inc.
Antelope Hollow State 32-20
1844' FNL & 2046' FEL
Sec. 20, T. 3 N., R. 19 E.
Daggett County, Utah

PAGE 12

13. REPRESENTATION

Anyone having questions concerning the APD should contact:

Brian Wood
Permits West, Inc.
37 Verano Loop
Santa Fe, NM 87508
(505) 466-8120 FAX: (505) 466-9682 Mobile: (505) 699-2276

The field representative will be:

Mark Stringfield
Noble Energy, Inc.
100 Glenborough Dr., Suite 100
Houston, TX 77067-3610
(281) 876-6150 FAX: (281) 872-2555 Mobile: (281) 799-2303

December 2, 2004

Affidavit of Surface Use Agreement

A Surface Use Agreement dated November 17, 2004 exists by and between Noble Energy, Inc. and Circle Bar Ranch covering the use of land connected with the Antelope Hollow State 32-20 well located in the SW/4 NE/4 of Section 20, T3N-R19E, Daggett County, Utah.

Noble Energy, Inc. agrees to abide by the terms and conditions of said Surface Use Agreement.


On behalf of Noble Energy, Inc.:

Jack E. Anderson
Jack E. Anderson
Senior Negotiator

State of Texas)
) ss:
County of Houston)

Subscribed and sworn to before me this 2ND day of December, 2004 by Jack E. Anderson.


Witness my hand and notarial seal.




Patricia A. Champion
Notary Public
State of Texas

My commission expires:


2-22-2006





Name: JESSEN BUTTE
 Date: 11/10/2004
 Scale: 1 inch equals 2000 feet

Location: 040.9717544° N 109.8079907° W
 Caption: 20, 3N-19E



RIFFIN & ASSOCIATES, INC.

1414 ELK ST., SUITE 202
ROCK SPRINGS, WY 82901
(307) 362-5028

SCALE: 1" = 60'

JOB No. 11910


DATE: 11/29/04

NOBLE ENERGY, INC.

ANTELOPE HOLLOW STATE 32-20

ESTIMATED EARTHWORK

ITEM	CUT	FILL	TOPSOIL	EXCESS
PAD	5540 CY	5453 CY	2223 CY	2310 CY
PIT	4463 CY			4463 CY
TOTALS	10003 CY	5453 CY	2223 CY	6773 CY



RIFFIN & ASSOCIATES, INC.

**NOBLE ENERGY, INC.
 ANTELOPE HOLLOW STATE 32-20**


1414 ELK ST., SUITE 202
 ROCK SPRINGS, WY 82901
 (307) 362-5028

JOB No. 11910


DATE: 11/29/04

SCALE: 1" = 60'


EXHIBIT 2A



A



B



C



RIFFIN & ASSOCIATES, INC.

1414 ELK ST., SUITE 202
ROCK SPRINGS, WY 82901
(307) 362-5028

JOB No. 11910



DATE: 11/29/04

NOBLE ENERGY, INC.
ANTELOPE HOLLOW STATE 32-20

HORZ. 1" = 60' VERT. 1" = 10'


UNGRADED ELEVATION: 7083.2'
FINISHED ELEVATION: 7091.2'

EXHIBIT 3




TYPICAL 5,000 psi WORKING PRESSURE BOP STACKS

- A = Annular type blowout preventer
- R = Ram
- S = Drilling spool with side outlet connections for choke & kill lines



10M AND 15M CHOKE MANIFOLD EQUIPMENT — CONFIGURATION MAY VARY



TYPICAL 10,000 psi WORKING PRESSURE BOP ARRANGEMENTS

A = Annular type blowout preventer
 S = Drilling spool with side outlet connections for choke & kill lines

G = Rotating Head

R = Ram

PERMITS WEST, INC.
 PROVIDING PERMITS for the ENERGY INDUSTRY

WORKSHEET

APPLICATION FOR PERMIT TO DRILL

003

APD RECEIVED: 12/06/2004

API NO. ASSIGNED: 43-009-30065

WELL NAME: ANTELOPE HOLLOW ST 32-20

OPERATOR: NOBLE ENERGY INC (N2345)

CONTACT: BRIAN WOOD

PHONE NUMBER: 505-466-8120

PROPOSED LOCATION:

SWNE 20 030N 190E

SURFACE: 1844 FNL 2046 FEL

BOTTOM: 1844 FNL 2046 FEL

DAGGETT

WILDCAT (1)

LEASE TYPE: 3 - State

LEASE NUMBER: ML-47543

SURFACE OWNER: 4 - Fee

PROPOSED FORMATION: MRSN

COALBED METHANE WELL? NO

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	DWD	12/28/04
Geology		
Surface		

LATITUDE: 40.98264

LONGITUDE: -109.8061

RECEIVED AND/OR REVIEWED:

- ☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[]
 (No. 10313458)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
 (No. 41-3160)
☐ RDCC Review (Y/N)
 (Date: 12/22/2004)
☒ Fee Surf Agreement (Y)N

LOCATION AND SITING:

R649-2-3.

Unit _____

- ☒ R649-3-2. General
 Siting: 460 From Qtr/Qtr & 920' Between Wells

R649-3-3. Exception

Drilling Unit

Board Cause No: _____

Eff Date: _____

Siting: _____

R649-3-11. Directional Drill

COMMENTS:


Needs Permit (Rec'd 12-16-04)

STIPULATIONS:

1- Spacing 57P

2- In accordance with R649-3-7-4, the 13 7/8" Surface casing shall be tested to 2100 psi and the 9 5/8" Intermediate casing shall be tested to 5700 psi.

3. STATEMENT OF BASIS




OPERATOR: NOBLE ENERGY INC (N2345)

SEC. 20 T.3N R.19E

FIELD: WILDCAT (001)

COUNTY: DAGGETT

SPACING: R649-3-2 / GENERAL SITING



Utah Oil Gas and Mining

Wells

- ✦ GAS INJECTION
- ✧ GAS STORAGE
- ✕ LOCATION ABANDONED
- ⊕ NEW LOCATION
- ✧ PLUGGED & ABANDONED
- ✧ PRODUCING GAS
- PRODUCING OIL
- ✧ SHUT-IN GAS
- ✧ SHUT-IN OIL
- ✕ TEMP. ABANDONED
- TEST WELL
- △ WATER INJECTION
- ◆ WATER SUPPLY
- ♠ WATER DISPOSAL

Units.shp


- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Fields.shp

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED



PREPARED BY: DIANA WHITNEY
DATE: 7-DECEMBER-2004



0 700 1400 2100 2800 ft

Water Rights

WR Number	Diversion Type/Location	Well Log	Status	Priority	Uses	CFS	ACFT	Owner Name
<u>41-1398</u>	Surface S660 W280 NE 20 3N 19E SL		P	1896	IS	0.110	0.000	CIRCLE BAR RANCH MANILA UT 84046
<u>41-1443</u>	Underground N80 E2485 W4 21 3N 19E SL		P	19300000	DS	0.011	0.000	BRANSON B. & EVELYN G. NEFF 2516 EVERGREEN AVENUE
<u>41-2142</u>	Surface N295 E680 SW 20 3N 19E SL		P	1896	IS	0.500	0.000	CIRCLE BAR RANCH MANILA UT 84046
<u>41-2143</u>	Surface S290 W1270 NE 30 3N 19E SL		P	18960300	IS	0.500	0.000	CIRCLE BAR RANCH MANILA UT 84046
<u>41-225</u>	Surface N380 W960 SE 18 3N 19E SL		P	18960000	IS	2.000	0.000	CIRCLE BAR RANCH MANILA UT 84046
<u>41-226</u>	Surface S450 W360 NE 30 3N 19E SL		P	18960300	DIS	0.500	0.000	SHEEP CREEK IRRIGATION COMPANY C/O ALBERT NEFF
<u>41-227</u>	Surface S200 E1035 NW 29 3N 19E SL		P	18960000	DIS	0.200	0.000	SHEEP CREEK IRRIGATION COMPANY C/O ALBERT NEFF
<u>41-2355</u>	Surface S1320 E745 N4 20 3N 19E SL		P	18960300	IS	0.250	0.000	CIRCLE BAR RANCH MANILA UT 84046
<u>41-257</u>	Surface N1040 W1990 E4		P	18960000	IS	2.000	0.000	CIRCLE BAR RANCH

Water that will be used for drilling maybe

Well ID	Surface/Underground	Priority	Water Right Number	Acres	Feet	Owner	Location
41-262	Surface	P	18960300 DIS	0.100	0.000	A UTAH CORPORATION FORREST D. PALLESEN FAMILY LIVING TRUST	17 3N 19E SL N470 W320 SE 20 3N 19E SL UT
41-263	Surface	P	18960300 IS	0.004	0.000	FORREST D. PALLESEN FAMILY LIVING TRUST	N205 W660 SE 20 3N 19E SL UT
41-264	Surface	P	18960300 IS	0.112	0.000	FORREST D. PALLESEN FAMILY LIVING TRUST	S355 W1160 NE 29 3N 19E SL UT
41-3090	Surface	U	19650603 DS	0.100	0.000	WILLIAM AND AGNES BRIGGS	N1850 E200 S4 21 3N 19E SL MANILA UT 84046
41-3100	Underground	P	19660506 DI	0.015	0.000	CIRCLE BAR RANCH	N1000 E850 S4 19 3N 19E SL MANILA, UT 84046
41-3158	Underground	P	19691209 DIS	0.033	0.000	CIRCLE BAR RANCH	S650 E1120 N4 30 3N 19E SL MANILA UT 84046
41-3159	Underground	P	19691209 DIS	0.015	0.000	CIRCLE BAR RANCH	S3520 E1250 NW 20 3N 19E SL MANILA UT 84046
41-3160	Underground	P	19691209 DIS	0.015	0.000	CIRCLE BAR RANCH	S3830 W1250 NE 19 3N 19E SL MANILA UT 84046
41-3163	Surface	P	18790000 IS	0.750	0.000	CIRCLE BAR RANCH	

	N920 W1600 SE 18 3N 19E SL				MANILA UT 84046
<u>41-3163</u>	Surface	P	18790000 IS	0.750 0.000	CIRCLE BAR RANCH
	N1745 W775 SE 18 3N 19E SL				MANILA UT 84046
<u>41-3175</u>	Underground	P	19720622 DIS	0.015 0.000	K. A. & BEULAH E. TURNER
	N2090 E1760 SW 21 3N 19E SL				BOX 155
<u>41-3209</u>	Underground	P	19740129 DIS	0.015 0.000	CIRCLE BAR RANCH
	S1205 W50 E4 19 3N 19E SL				MANILA UT 84046
<u>41-3356</u>	Underground	A	19841226 DIS	0.015 0.000	JOSEPH F. & LETA O. WAHLQUIST
	N520 E520 S4 19 3N 19E SL				CIRCLE BAR RANCH
<u>41-451</u>	Underground	P	19300000 S	0.015 0.000	CIRCLE BAR RANCH
	S960 E225 W4 17 3N 19E SL				MANILA UT 84046

[Natural Resources](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)



State Online Services

Agency List

Business.utah.gov

Search Utah.gov

GO

UTAH DIVISION OF WATER RIGHTS

WRPLAT Program Output Listing

Version: 2004.11.16.00 Rundate: 12/15/2004 04:03 PM

Radius search of 5280 feet from a point S1844 W2046 from the NE corner, section 20, Township 3N, Range 19E, SL
b&m Criteria:wrtypes=W,C,E podtypes=S,U,D,Sp,P status=U,A,P usetypes=all

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: Noble Energy, Inc.

WELL NAME & NUMBER: Antelope Hollow State 32-20

API NUMBER: 43-009-30065

LEASE: State (ML-47543) **FIELD/UNIT:** Wildcat

LOCATION: 1/4, 1/4 SWNE **Sec:** 20 **TWP:** 3N **RNG:** 19E 1844' **FNL** 2046' **FEL**

LEGAL WELL SITING: 460 F **SEC. LINE;** 460 F **1/4, 1/4 LINE;** 920 F **ANOTHER WELL**

GPS COORD (UTM): GIS:X=600,440 E; Y=4,537,304 N; GPS:X=600,445E; Y=4,537,309N

SURFACE OWNER: George Olson, Circle Bar Ranch, Circle Bar Ranch Rd., Manila, UT

PARTICIPANTS

C. Kierst (DOGM), George Olson (Surface Owner), Brian Wood (Permits West), Joe Wahlquist (Daggett County), Jim Howell (with GSM representing Noble Energy) and several dirt contractors wanting to bid the job. Ed Bonner of SITLA was unable to attend owing to other conflicting onsite review commitments.

REGIONAL/LOCAL SETTING & TOPOGRAPHY

The proposed location is on property owned by George Olson, owner of the Circle Bar Ranch, located ~4½ miles west of Manila, Daggett County, Utah. The South Valley Canal system is within 600 feet to the south. The local terrain drains and slopes to the north into Wyoming and the Henry's Fork River via the Antelope Wash drainage. Within about ten miles the Henry's Fork River drains eastwardly into the Henry's Fork arm of Flaming Gorge Reservoir in the Flaming Gorge National Recreation Area (Green River drainage). The location is on the north flank of the Uinta Mountains and appears to be just north of the north flank fault system. Precambrian rocks of the Uinta Mountains are about 4½ miles south. It is near the southernmost extreme of the Green River Basin in an area called the Bridger Basin (subbasin?). The local area is ranch pasture in a broad sagebrush/pasture draw called Antelope Hollow that is at an elevation of about 7,000 feet.

SURFACE USE PLAN

CURRENT SURFACE USE: Irrigated pasture grazing and wildlife habitat.

PROPOSED SURFACE DISTURBANCE: 300' X 400' pad with inboard 190'X75'X12' pit. Cut and fill margins will expand the pad area slightly and there will be sufficient room for topsoil and pit material storage along the south and west edges of the location. Half a mile of new access road will be built. A 48" culvert will be installed to cross an ~10' deep drainage about 1,700' west of the pad.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: 1 PA well (4300930064) exists within a 1 mile radius of the above proposed well.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: Bermed production facilities will be placed on the cut portion of the pad. Gas pipelines

will have to be run to the north off the pad more or less down Antelope hollow.

SOURCE OF CONSTRUCTION MATERIAL: Gravel will be purchased from the permitted Harper pit about 3½ miles to the southwest. Fill material will come from an area on the Circle Bar Ranch itself.

ANCILLARY FACILITIES: N/A

WASTE MANAGEMENT PLAN:

Portable chemical toilets which will be emptied into an approved sewage disposal facility; garbage cans on location will be emptied into trash cages that be emptied into an approved landfill. Crude oil production will be placed in test tanks on location. Drilling fluid, completion / frac fluid and cuttings will be buried in the pit after evaporation and slashing of the pit liner. Used oil from drilling operations and support will be hauled to an approved used oil recycler.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: The immediate area is on a terrace or low prominence between two draws, Antelope Hollow, which opens to the north, and Birch Spring Draw, which opens to the east. Birch Spring Draw feeds into Flaming Gorge Reservoir within 10 miles. This area may be a recharge area. There are several ponds nearby and the location is situated between two that are about ½ mile distant. The South Valley Canal flows by within 1,000' to the south. The Jessen Butte topographic quadrangle depicts that several nearby small drainages also flow into the canal. One such drainage (a canal) contains live water (landowner says it's seepage not canal flow) and is about 500' to the south-southeast. The area most likely receives considerable inputs of high quality Uinta Mountains snowmelt water and the Bridger, Laney, New Fork and Fort Union aquifers in particular are likely to contain significant volumes of high quality water. Another drainage ~ 1,700' west of the location with flowing water in it may be a drainage ditch that flows to the bottomland for irrigation/livestock watering. The access road will cross the drainage and will use a 48" culvert to effect a crossing. Bob Leake of Division of Water Right's Vernal, Utah, office says the area south of the dogleg in the drainage is a drainage ditch rather than a natural drainage and therefore doesn't require a 404 Dredge & Fill Permit for the access road crossing.

FLORA/FAUNA: Sagebrush, native grass, cottonwood, willows, antelope, elk, deer, coyote, various fowl and small game.

SOIL TYPE AND CHARACTERISTICS: Moderately permeable sandy soil.

SURFACE FORMATION & CHARACTERISTICS: The Bridger Formation is exposed at the surface in the area, frequently with a thin soil cover on terraces and bottoms. The Tertiary, late Eocene age Bridger Formation is generally described as mudstone interbedded with crossbedded, tuffaceous mudstone although it may be locally conglomeratic (and sandy) in the southern part of the Green River Basin (such as this location). The Bridger Formation is identified as an aquifer geohydraulic unit by the

USGS.

EROSION/SEDIMENTATION/STABILITY: This area is not highly eroded or prone to bank instability. The worst slopes on the location present about 15' of elevation in 250' of surface (~6% grade), although the location is adjacent to a steeper terrace sloping to the north.

PALEONTOLOGICAL POTENTIAL: None observed

RESERVE PIT

CHARACTERISTICS: Dugout earthen pit. 190' X 75' X 12' (As per APD.)

LINER REQUIREMENTS (Site Ranking Form attached): Synthetic liner required. (As per APD.)

SURFACE RESTORATION/RECLAMATION PLAN

As per surface use agreement.

SURFACE AGREEMENT: Surface use agreement has been signed.

CULTURAL RESOURCES/ARCHAEOLOGY: None required by surface owner.

OTHER OBSERVATIONS/COMMENTS

Unit Drilling will be the drilling contractor. A diversion ditch will be placed on the south and west sides of the pad. The access road will enter the pad near the northwest corner at about the zero cut and fill point. A culvert will be placed where it crosses the diversion ditch. A 48" culvert will be installed to cross an ~10' deep drainage about 1,700' west of the pad. The operator will obtain his drilling water from George Olson's ranch water. The operator has a statewide surety blanket bond in place for plugging in the amount of \$120,000.

ATTACHMENTS

5 photos of this location were taken and will be placed on file.

Christopher J. Kierst
DOGM REPRESENTATIVE

12/16/2004 / 12:30 PM
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>15</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>2</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>10</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of hazardous constituents	20	<u>15</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>10</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>10</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>6</u>
Presence of Nearby Utility		
Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>

Final Score 68 (Level I Sensitivity)

Sensitivity Level I = 20 or more; total containment is required.

Sensitivity Level II = 15-19; lining is discretionary.

Sensitivity Level III = below 15; no specific lining is required.

**DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS**

OPERATOR: Noble Energy, Inc.
WELL NAME & NUMBER: Antelope Hollow State 32-20
API NUMBER: 43-009-30065
LEASE: State FIELD/UNIT: none
LOCATION: 1/4,1/4 SWNE Sec: 20 TWP: 3N RNG: 19E 1844' FNL 2046' FEL

Geology/Ground Water:

Significant volumes of high quality ground water are likely to be encountered at this location. A moderately permeable soil is likely to be developed on the Tertiary, late Eocene Bridger Formation in the area. Several nearby water supply wells that are documented in the Division of Water Rights database reveal that the water table was encountered between 10 and 140 feet of depth, most likely in the Bridger Formation. Mr. Olson, the landowner, related that it is common for wells in the area to have static water levels around 60' below ground level. No published base of moderately saline ground water information is available in this area. It is likely that there are several thousands of feet of high quality ground water saturated strata owing to the proximity of the area to the Uinta Mountains and the purported aquifer status of the near surface strata. The proposed drilling, casing and cementing program should adequately isolate any zones of fresh water that may be penetrated. Included among the several water rights filed within a mile of the location are six subsurface water rights for water supply wells, most of which are operated by the surface owner.

Reviewer: Christopher J. Kierst

Date: 12/17/2004

Surface:

The proposed location is on property owned by the Olson Family, operators of the Circle Bar Ranch, which is located ~4½ miles west of Manila, Daggett County, Utah. The unnamed drainage about 1,600' west of the flag was observed to contain flowing water. This drainage will receive a 48" culvert and require a 404 Dredge and Fill Permit for the access road crossing. The surface immediately surrounding this location drains north to the Henry's Fork River. Precipitation will be deflected around the location with a diversion ditch on the south and west sides, berms and culverts. The site will be fenced completely around the location. The site was photographed and characterized during the onsite review. Provision was made to ensure site rehabilitation, litter and waste control, preservation of drainage patterns and the integrity of local infrastructure, groundwater and other resources. The well utilities and gas gathering system will follow the approach roadway. Attendance the on-site was George Olson representing the Circle Bar Ranch and Joe Wahlquist representing Daggett County.


Reviewer: Christopher J. Kierst

Date: 12/17/2004

Conditions of Approval/Application for Permit to Drill:

1. Culverts sufficient to manage expected runoff, standing and surface water in crossed drainages.
2. Berm location and pit.
3. A synthetic liner with a minimum thickness of 12 mils shall be properly installed and maintained in the reserve pit.

STATE ACTIONS
Resource Development Coordinating Committee
Governor's Office of Planning and Budget
5110 State Office Building
SLC, UT 84114
Phone No. 537-9230

1. State Agency Oil, Gas and Mining 1594 West North Temple, Suite 1210 Salt Lake City, UT 84114-5801	2. Approximate date project will start: Upon Approval or December 21, 2004
3. Title of proposed action: Application for Permit to Drill	
4. Description of Project: Noble Energy, Inc. proposes to drill the Antelope Hollow State 32-20 well (wildcat) on State lease ML-47543, Daggett County, Utah. This action is being presented to the RDCC for consideration of resource issues affecting state interests. The Division of Oil, Gas and Mining is the primary administrative agency in this action and must issue approval before operations commence.	
5. Location and detailed map of land affected (site location map required, electronic GIS map preferred). (include UTM coordinates where possible) (indicate county) 1844' FNL 2046' FEL, SW/4 NE/4, Section 20, Township 3 North, Range 19 East, Daggett County, Utah	
6. Possible significant impacts likely to occur: Surface impacts include up to five acres of surface disturbance during the drilling and completion phase (estimated for five weeks duration). If oil and gas in commercial quantities is discovered, the location will be reclaimed back to a net disturbance of between one and two acres – not including road, pipeline, or utility infrastructure. If no oil or gas is discovered, the location will be completely reclaimed.	
7. Identify local government affected a. Has the government been contacted? No. b. When? c. What was the response? d. If no response, how is the local government(s) likely to be impacted?	
8. For acquisitions of land or interests in land by DWR or State Parks please identify state representative and state senator for the project area. Name and phone number of state representative, state senator near project site, if applicable: a. Has the representative and senator been contacted? N/A	
9. Areawide clearinghouse(s) receiving state action: (to be sent out by agency in block 1) Uintah Basin Association of Governments	
10. For further information, contact: Diana Whitney Phone: (801) 538-5312	11. Signature and title of authorized officer  John R. Baza, Associate Director Date: December 7, 2004

Well name:

12-04 Noble Energy Antelope Hollow St 32-20Operator: **Noble Energy Inc.**String type: **Surface**

Project ID:

43-009-30065

Location: **Dagget County****Design parameters:****Collapse**Mud weight: 8.300 ppg
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 103 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 250 ft

Cement top: Surface

BurstMax anticipated surface
pressure: 1,760 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,000 psi

No backup mud specified.

Tension:8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)Tension is based on buoyed weight.
Neutral point: 1,752 ft

Non-directional string.

Re subsequent strings:Next setting depth: 10,000 ft
Next mud weight: 8.900 ppg
Next setting BHP: 4,623 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,000 ft
Injection pressure 2,000 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2000	13.375	61.00	J-55	Buttress	2000	2000	12.39	242.8
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	862	1540	1.786	2000	3090	1.55	107	962	9.00 B

Prepared Clinton Dworshak
by: Utah Div. of Oil & MiningPhone: 801-538-5280
FAX: 801-359-3940Date: December 23, 2004
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 2000 ft, a mud weight of 8.3 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

12-04 Noble Energy Antelope Hollow St 32-20Operator: **Noble Energy Inc.**

String type: Intermediate

Project ID:

43-009-30065

Location: Dagget County

Design parameters:**Collapse**

Mud weight: 8.900 ppg

Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 215 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,500 ft

Cement top: 7,824 ft

Burst

Max anticipated surface pressure:

8,800 psi

Internal gradient: 0.120 psi/ft

Calculated BHP 10,000 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.

Neutral point: 8,665 ft

Re subsequent strings:

Next setting depth: 18,500 ft

Next mud weight: 12.000 ppg

Next setting BHP: 11,532 psi

Fracture mud wt: 19.250 ppg

Fracture depth: 10,000 ft

Injection pressure 10,000 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	10000	9.625	47.00	S-95	LT&C	10000	10000	8.625	942.5

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	4623	7100	1.536	10000	8150	0.81	407	1053	2.59 J

Prepared by: Clinton Dworshak
Utah Div. of Oil & MiningPhone: 801-538-5280
FAX: 801-359-3940Date: December 23, 2004
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 10000 ft, a mud weight of 8.9 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	12-04 Noble Energy Antelope Hollow St 32-20	
Operator:	Noble Energy Inc.	Project ID:
String type:	Production	43-009-30065
Location:	Dagget County	

Design parameters:
Collapse

Mud weight: 12.000 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 334 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 8,828 ft

Burst

Max anticipated surface pressure: 9,312 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 11,532 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.
Neutral point: 15,176 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	18500	5.5	23.00	P-110	LT&C	18500	18500	4.545	851.7
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	11532	14540	1.261	11532	13580	1.18	349	643	1.84 J

Prepared by: Clinton Dworshak
Utah Div. of Oil & Mining

Phone: 801-538-5280
FAX: 801-359-3940

Date: December 23, 2004
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 18500 ft, a mud weight of 12 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

12004 Noble Energy Antelope Hollow St 32-20

Casing Schematic

Surface

13-3/8"
MW 8.3
Frac 19.3

BHW

$$(.052)(18,500)(12) = 11,544$$

Anticipate 9100

Gw

$$(.12)(18,500) = 2220$$

$$MHSR = 9334$$

9-5/8"
MW 8.9
Frac 19.3

BORE - 5,000 To 10,000'
10,000' # 10,000' TO TD ✓

Surf Csg - 3090

$$70\% = 2163$$

Propose test to 1000psi → inadequate

max press @ shoe (2868psi)

Int Csg - 8150

$$70\% = 5707$$

propose test to 2200psi → inadequate

using G.P. max BHP max press @ shoe = (7230psi)

Adequate w/ required Test pressures

DND 12/28/04

5-1/2"
MW 12.

TOC @
0 Green River 263'

67 18% w/shoot

Surface
2000. MD

Washok 2863

TOC To
protect Washok

Amended
Cement
Program
12/27/04

Fort Union 5863

W. Tied Coals

TOC @
7823.

TOC @
8828.

TOC Test 9234'

67 15% w/shoot

5484' w/ 0% w/shoot

Intermediate
10000. MD

H. Mound
10,063

Clabrador 14,034

D. Keta 17,790

Production
18500. MD

Project Number: 4726 Sponsor: Division of Oil, Gas and Mining
SLB&M: Sec. 20, T3N, R19E Counties Affected: Daggett
Description: Application for Permit to Drill - proposal to drill a wildcat well, the Antelope
Hollow State 32-30 on State lease ML-47543
Comments Due to Sponsor 12/23/2004

Implementation of this project may involve considerable disturbances and alterations to the existing environment. To minimize the possible negative impacts, the leasor should be required to reduce negative environmental impacts of the project resulting from erosion and damage to vegetation and habitat.

These three provisions would include:

- 1- Restore vegetative cover to levels equal to or exceeding the cover existing prior to project activity, or to whatever levels are necessary to insure erosion rates from the total disturbed area are maintained below the NRCS tolerable soil loss rates.. Vegetation planted or restored should be primarily native species and must not include any invasive species.
- 2- Project roadways, pads, drilling sites, pipeline placements and all other ground disturbing activities should be designed, engineered, and implemented to minimize crossing of or disturbance to streams, washes, gullies, arroyos, or other depressions or sites where resulting erosion potential would be high.
- 3- Roads installed or maintained for the project should be constructed in accord with the road hydrostrip standards adopted and required for use within the BLM Price, Utah Office Management area. These Hydrologic Modification Standards for Roads significantly reduce problematic erosion and gulying. Although adherence to the standards initially requires some slightly higher installation costs, the long term costs of maintenance, upkeep, and of roads made impassable under adverse conditions is reduced so significantly as to provide very strong financial benefits to their implementation, in addition to the environmental benefits.

These Price Field Office Hydrologic Modification Standards for Roads are copied below.

Price Field Office
Hydrologic Modification Standards for Roads
K. Flood – Hydrologist
Updated October 14, 2003

I. Surface Water Channel Crossing Criteria:

- (1) Crossings which require a CWA-404 or GP-40 channel alteration permit, as determined by the Utah Division of Water Rights, are to be engineered if they are part of a federal Right of Way permit application.

- (2) Channel crossings requiring culverts with individual or cumulative diameters of 30 inches or greater are to be engineered, and sized to the 25 year, 6 hour event at a minimum.

A. The commonly used sizing equations for culverts or other flow conveyances might not be reliable if there are no local precipitation stations from which to obtain accurate values. Isohyets are generated from available data. Often, the isohyet values given for remote areas have large errors associated with them. In such cases, run-off and stream flows should be obtained from hydrographs if available, measured directly if possible, or estimated based on channel dimension measurements.

- (3) Wherever possible, roads should be aligned perpendicular to channels at crossings.
- (4) Crossings on perennial channels which require structures or channel modification, including bank disturbance, are to be engineered. Crossings on intermittent and ephemeral channels may require engineering on a case by case basis.
- (5) Culverts should connect a channel at existing points on both sides of the road. Realignment of channels is strongly discouraged. If realignment is the only option, engineering shall be done to ensure channel parameters are preserved as described in I. (6) A, B, and C.
- (6) Engineered designs will ensure that crossings do not cause changes to the existing channel parameters as follows:

A. Cross Sectional Dimensions: Changes to the cross sectional dimensions of a channel destabilize streams. An altered channel often undergoes a series of undesirable changes before restabilizing. Significant widening and downcutting can occur, followed by the formation of a new channel within the widened area. This process results in significant soil loss, degrading water quality. Local ground water levels are often lowered, which can cause changes in vegetation.

1. width, as measured at bankfull level: Factors which influence width are:

a. flow velocity: Velocity of flow exiting the crossing must equal velocity of flow entering the crossing. Where culverts are used, a >V= shaped flow guide (i.e., wing walls) should be installed at the inlet. At the outlet, a >U= shaped guide should be used to return flow to the original width, depth, and velocity. Also see criteria I. (6) A. 1. d. and I. (6) A. 2. b.

- b. flow magnitude: Avoid changes in flow magnitude within the channel. Where a flood plain is present, flows from the flood plain must not be converged with channel flow. Each flood plain must be reestablished at the crossing outlet, with flow discharged at the same velocity, width, and depth as found immediately upstream of the inlet. Where culverts are used, the flood plains should have individually sized culverts, and each must be properly placed. Combination culvert/low-water crossings may be used, allowing flood level flows to go over the road. The same principles apply, differences in flow velocity on the flood plains must be considered in crossing designs. See I. (6) A. 2. a. and I. (6) A. 2. b.
 - c. size and type of transported sediment: Avoid creating changes in sediment load via use of erosion controls during construction and by replacing vegetation as soon after construction as possible.
 - d. bed and bank materials: Introduced bed and/or bank materials should have a friction coefficient similar to that of the natural channel, except where specifically designed to adjust flow velocity, and must be installed so as to withstand high flows and floods without dislodging.
2. depth, as measured from thalweg to bankfull level: The practice of installing culverts at a slope less than the natural channel bed slope to adjust flow velocity should be discontinued if changes to channel depth are to be avoided. This would also serve to reduce head at the inlet which can occur from the flow velocity change caused by the difference in culvert slope and bed slope.
- a. Culverts should generally be installed with approximately ten percent of the diameter below the channel bed, provided rock or concrete aprons are included at the inlet and outlet, each flush with the original bed surface. Unless the bed is armored, both the inlet and the outlet must be installed at the existing bed level. Exceptions to this may be prescribed to reverse a preexisting downcutting problem without incurring additional costs.
 - b. Adjust flow velocity using an energy dissipating rock apron at the outlet.

B. Stream Channel Patterns:

1. radius of curvature: The following equation gives a relationship for the radius of curvature of meander bends to meander length and sinuosity.

$$R = L_m K^{-1.5} + 13(K-1)^{0.5}$$

where: R = radius of curvature
L_m = meander length

$K = \text{sinuosity}$

and: $K = L_c / L_v$; which may be approximated by m_v / m_c

where: L_c = channel length
 L_v = valley length
 m_v = valley slope
 m_c = channel slope

This relationship shows that parameters of a realignment can be made to mimic natural pattern geometry by adjusting channel slope and length within the realignment reach. It is necessary to design channel pattern changes (realignments) using the correct radius of curvature to avoid causing repercussions to the cross sectional dimensions. However, realignments should be made only if there are no alternatives. See I. (6) C. 1.

- a. In cases where a channel must be realigned, the radius of curvature of the new alignment must equal the radius of curvature of the natural meander of the channel.

2. width/variable width, as a function of depth:

- a. Width at bankfull of the new reach must equal width at bankfull of the original reach.
- b. Banks must be contoured with the same slope as the original banks.

C. Stream Channel Profile:

1. slope of the channel bed: The bed slope is the single most sensitive physical parameter of a channel. When the bed slope changes, most or all other parameters of the pattern and cross sectional dimensions will change.
 - a. If possible, choose a crossing location low on the watershed, where the ground is relatively flat. See criteria I. (6) A. 2. a. and I. (6) A. 2. b.
2. pool-riffle ratio: At higher elevations in a watershed, the bed slope is generally greater and the channel is usually straighter (lower sinuosity). To compensate for low sinuosity, step pools and riffles develop at more frequent intervals. Pools occur where the bed slope is flatter, and riffles occur where the slope increases. Also, water seeps into the ground at pools, and discharges from the ground into the channel at riffles. If

structures are built on riffles, water seepage could cause extensive damage and present potential safety risks.

- a. Cross channels at pools, not at riffles.
- b. Where roads must cross at riffles, in-seepage of water must be addressed in the design.

II. Road Drainage Criteria: Roads which run perpendicular to hill slopes act as berms, capturing sheet flow from runoff and snowmelt and converting it into channel flow along the road. This diverts water from areas immediately downslope of the road, which can cause undesirable changes in vegetation. Ditches which are typically built along roads to transport this channelized runoff are often discharged at the nearest existing wash, stream channel or low point on the terrain. Where this discharge occurs at a channel crossing (usually the downstream side of the crossing) severe erosion frequently results. Channels are significantly widened below such crossings, appearing as blown out. See Criteria 1. (6) A. 1. b. Also, road ditches often create severe erosion gullies by headcutting back from the wash. Where roads run parallel to channels, ditched runoff is often discharged or turned-out toward the channel at low points along the road. This frequently results in erosive headcuts forming from the channel to the road. This erosion degrades water quality, can destabilize the receiving channel, often erodes the road surface, and can block access along a channel. The type of damage described can be minimized or prevented with little additional cost incurred.

- (1) Road drainage flow should not be converged with existing channel flow.
- (2) Ditch turnouts should be made along the road at locations where terrain is fairly level along the road, and which slopes gently away from the road.
- (3) Turnouts should be equipped with gravel or rock aprons at each outlet. The apron should:
 - A. expand outward away from the outlet for a distance sufficient to disperse channel flow from the ditch back into sheet flow
 - B. reduce flow velocity enough to prevent rill formation.
- (4) Turnouts should be placed as needed to avoid transferring water from one drainage basin or subbasin to another, and to effect as complete a return to the original flow regime as practical. Spacing criteria as specified in the Class III road standards used by the PFO are the minimum standard.

III. Miscellaneous Construction Phase Criteria:

- (1) For activities which disturb one (1) or more acres, a Storm Water Pollution Prevention Plan (SWPPP) must be submitted to the Utah Department of Environmental Quality.
- (2) The Best Management Practices (BMPs) set forth in the Utah Nonpoint Source Management Plan for Hydrologic Modifications, Appendix B., page 3 should be implemented as applicable.
- (3) In the event construction can't be completed prior to winter closures, measures to prevent erosion from upcoming spring snowmelt should be taken as follows:

A. Loose earth and debris must be removed from drainages, and flood plains.

B. Earth and debris should not be stockpiled on drainage banks.

C. Road drainages should be checked to ensure there are none with uncontrolled outlets.

1. Be sure all ditch drainages have an outlet to prevent ponding.
2. If necessary, build temporary sediment ponds to capture runoff from unreclaimed areas.
3. Re-route ditches as needed to avoid channeling water through loosened soil.

From: Robert Clark
To: Whitney, Diana
Date: 12/15/2004 9:07:08 AM
Subject: Comments on Antelope Hollow State 32-20 Wildcat Well

The following comments are submitted from the Division of Air Quality regarding the Antelope Hollow State 32-20 Wildcat Well in Daggett County.

Comments begin: The proposed well drilling project may require a permit, known as an Approval Order, from the Utah Division of Air Quality if any compressor stations are operating at the site. A permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, SLC, UT, 84116 for review according to the Utah Air Conservation Rule R307-400, Permits, Notice of Intent and Approval Order.

The proposed project is also subject to Utah Air Conservation Rule R307-205-3, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Division of Air Quality, but steps need to be taken to minimize fugitive dust, such as, watering and/or chemical stabilization, providing vegetative or synthetic cover and windbreaks. A copy of the rules are found at www.rules.utah.gov/publicat/code/r307/r307.htm . **Comments end.**

CC: Dave Mcneill; Wright, Carolyn



State of Utah

Department of
Natural Resources

ROBERT L. MORGAN
Executive Director

Division of
Oil, Gas & Mining

MARY ANN WRIGHT
Acting Division Director

OLENE S. WALKER
Governor

GAYLE F. McKEACHNIE
Lieutenant Governor

December 28, 2004

Noble Energy, Inc
100 Glenborough
Houston, TX 77067-3610

Re: Antelope Hollow State 32-20 Well, 1844' FNL, 2046' FEL, SW NE, Sec. 20,
T. 3 North, R. 19 East, Daggett County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-009-30065.

Sincerely,

A handwritten signature in black ink, appearing to read "John R. Baza".

(for) John R. Baza
Associate Director

pab
Enclosures

cc: Daggett County Assessor
SITLA

Operator: Noble Energy, Inc
Well Name & Number Antelope Hollow State 32-20
API Number: 43-009-30065
Lease: ML-47543

Location: SW NE Sec. 20 T. 3 North R. 19 East

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

6. Operator shall comply with applicable recommendations resulting from Resource Development Coordinating Committee review. Statements attached.

7. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
8. In accordance with R649-3-7-4, the 13 3/8" surface casing shall be tested to 2100 psi and the 9 5/8" intermediate casing shall be tested to 5700 psi.

DIVISION OF OIL, GAS AND MINING**SPUDDING INFORMATION**Name of Company: NOBLE ENERGY INCWell Name: ANTELOPE HOLLOW ST 32-20Api No: 43-009-30065 Lease Type: STATESection 20 Township 03N Range 19E County DAGGETTDrilling Contractor PETE MARTIN'S RIG # BUCKET**SPUDDED:**Date 01/09/05Time How DRY**Drilling will commence:** Reported by JIM HOWELLTelephone # 1-435-784-3564Date 02/02/2005 Signed CHD

006

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

RECEIVED

FEB 0 / 2005

FORM 6

ENTITY ACTION FORMOperator: Noble Energy, Inc.Operator Account Number: N-2345Address: 100 Glenborough Dr., #100city Houstonstate Texas zip 77067Phone Number: 281-874-6765**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
43-009-30065	Antelope Hollow State 32-20		SWNE	20	3N	19E	Daggett
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	14556	02/02/2005				
Comments: Well Spud @8:00 p.m. 2/2/2005. Conductor set @ 100'. Encountered Fresh Water @ 60'. <i>MRSN</i>							

K

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Patricia Jaenecke
Name (Please Print)
Patricia Jaenecke
Signature
Sr. Reg. Specialist
Title

02/03/2005
Date

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
2. NAME OF OPERATOR: Noble Energy, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 100 Glenborough CITY Houston STATE TX ZIP 77067		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S		8. WELL NAME and NUMBER: Antelope Hollow State 32-20
PHONE NUMBER: (281) 874-6765		9. API NUMBER: 43-009-30065
		10. FIELD AND POOL, OR WILDCAT: Wildcat
		COUNTY: Daggett
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Weekly Progress Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

02/02/2005 - Well Spud @8:00 p.m. 2/02/2005. Conductor set @ 100'. Encountered Fresh water @ 60'. Drilled to 244'.
02/03/2005 - Drilled to 603'. Circulated. Washed 45' to btm. Drill to 633'.
02/04/2005 - Drilled to 786'. Replaced swivel. Drilled to 1109'. Ran wireline survey @ 1022'. Drilled to 1184'.
02/05/2005 - Service rig. Drilled to 1587'. Ran wireline survey @1500'. Drilled to 1980'.
0206/2005 - Made wiper trip. Mix & pump Hi-Vis Sweep. RU Frank's Westate csg equipment. Ran 44 jts 13 3/8", 61#, J-55
BTC surface csg. RU BJ cementing head. RD Frank's. Cement surface csg.

NAME (PLEASE PRINT) Patricia Jaenecke

TITLE Sr. Regulatory Specialist

SIGNATURE

DATE 2/7/2005

(This space for State use only)

RECEIVED
FEB 10 2005
DIV. OF OIL, GAS & MINING

008

DOUBLE JACK TESTING & SERVICES/IPS

Phone (307) 789-9213

B.O.P TEST REPORT

B.O.P. TEST PERFORMED ON (DATE) 2/8&9/05

OIL COMPANY NOBLE

WELL NAME & NUMBER ANTELOPE HOLLOW STATE #32-20 43-009-30065 T03N R19E S-20

SECTION 20

TOWNSHIP 3 N

RANGE 19 E

COUNTY & STATE DAGGET UTAH

DRILLING CONTRACTOR UNIT DRLG RIG #166

OIL COMPANY SITE REPRESENTATIVE J. HOWELL

RIG TOOL PUSHER _____

TESTED OUT OF Evanston, Wyoming

NOTIFIED PRIOR TO TEST _____

COPIES OF THIS TEST REPORT SENT TO: STATE OF UTAH DIVISION OF OIL, GAS & MINING

UTAH BUREAU OF LAND MANAGEMENT

ORIGINAL CHART & TEST REPORT ON FILE AT:

DOUBLE JACK TESTING & SERVICES, INC.

PO BOX 2097

EVANSTON, WY 82930

TESTED BY: JOE BRUCE & GARY THOMPSON

RECEIVED

FEB 14 2005

DIV. OF OIL, GAS & MINING

Double Jack Testing & Services Inc.

FIELD TICKET

No 18913

Accounting Office: P.O. Box 516 Shoshoni, WY 82649 • (307) 876-9390

Field Operations: Shoshoni, WY (307) 876-2308
 Evanston, WY (307) 789-9213
 Rock Springs, WY (307) 382-4020
 Big Piney, WY (307) 276-5265
 Vernal, UT (435) 781-0448

DATE 2-8, +9-05
☒ OPERATOR Noble
☐ CONTRACTOR Unit Drilling Rig #166
 WELL NAME Antelope Hollow State #32

COUNTY Daguer STATE WY. SECTION 20 TOWNSHIP 3N. RANGE 19E.

Items Tested:

	LOW TEST PSI	TIME HELD MINUTES	HIGHEST PSI	TIME HELD MINUTES	
Top Pipe Rams	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	Closing Unit PSI <u>1,300</u>
Bottom Pipe Rams	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	Closing Time of Rams <u>9 SECS.</u>
Blind Rams	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	Closing Time of Annular <u>19 SECS.</u>
Annular B.O.P.	<u>250</u>	<u>5</u>	<u>3,500</u>	<u>10</u>	Closed Casing Head Valve <u>yes</u>
Choke Manifold	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	Set Wear Sleeve
Choke Line valves	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	
Kill Line valves	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	
Super Choke	<u>N/A</u>	<u>N/A</u>	<u>5,000</u>	<u>1</u>	
Upper Kelly	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	
Lower Kelly	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	
Floor Valve	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	
Dart Valve	<u>250</u>	<u>5</u>	<u>5,000</u>	<u>10</u>	
Casing	<u>N/A</u>	<u>N/A</u>	<u>2,100</u>		

COMMENTS

ADDITIONAL TESTS & COMMENTS

	TEST PLUG	CHARGES
	TOP SUB.	<u>\$55.00</u>
	KELLY SUB.	<u>\$55.00</u>
	X-OVER SUB.	
	OTHER	

QUANTITY

RATES

<u>Unit</u>	UNIT RATES	<u>to test B.O.P.s + valves for 1st 7 M.F.</u>	<u>\$1,100.00</u>
<u>18 Hrs.</u>	ADDITIONAL	<u>time over set up charge @ \$85.00</u>	<u>\$1,530.00</u>
<u>180 miles</u>	MILEAGE	<u>to + from location @ \$2.10 per mile</u>	<u>\$378.00</u>
<u>310</u>	OTHER	<u>Anti-Freeze Fluid 50/50 Mix @ \$2.00</u>	<u>\$620.00</u>
<u>2 flanges</u>	OTHER	<u>Charge to torque choke manifold valves @ \$150.00 per flange</u>	<u>\$300.00</u>

Joe Bruce, Gary Thompson

SUBTOTAL \$4,038.00

PURCHASE ORDER #

TESTED BY

NO ACCIDENTS

TAX

COMPANY REPRESENTATIVE

DOUBLE JACK TESTING UNIT NUMBER

TOTAL

NOTICE TO ALL CUSTOMERS


If this account shall not be paid when due and it is placed with an attorney for collection, or if suit be instituted for collection, the undersigned agree(s) to pay in either case, reasonable expense of collection including attorney's fees and court cost in compliance with TRUTH IN LENDING AND THE UNIFORM CONSUMER CREDIT CODE, the following information disclosure, under the terms of our regular accounts, all amounts for service due and payable within THIRTY (30) DAYS from the receipt of an invoice for such services. A LATE CHARGE will be assessed when accounts are not paid when due. THE LATE CHARGE is computed by a "periodic rate" 1-3/4% PER MONTH which is an ANNUAL PERCENTAGE RATE OF 21% to the previous balance in the account on the billing date. No further credit can be extended on unpaid delinquent accounts until the delinquent account is paid in full. The contractor will not be held liable for damages caused by acts of God, or unforeseen circumstances that could not be reasonably anticipated in performing the work done as set forth above.

DOUBLE JACK TESTING & SERVICES/IPS

[illegible]

10000-15000-20000 PSI

Noble
Unit Dig. Rig #166
Antelope Hollow State 32
2-9-05



DOUBLE JACK TESTING

IPS / Double Jack Testing

Accumulator Function Tests

- # 1 RECORD INITIAL ACCUMULATOR PRESSURE 3,000
 # 2 WITH DRILL PIPE & TEST PLUG INSTALLED IN WELL HEAD.
 # 3 PLACE ALL FUNCTIONING ACCUMULATOR VALVES IN OPEN POSITION
 ALLOW ACCUMULATOR TO PRESSURE UP BEFORE SHUTTING OFF ALL PUMPS
 # 4 CLOSE ANNULAR / RECORD TIME & PRESSURE.

ANNULAR INTIAL PSI 3,200 FINAL PSI 2,400 TIME 19 secs

- #5 CLOSE PIPE RAMS / RECORD TIME & PRESSURE.

PIPR RAMS INTIAL PSI 2,400 FINAL PSI 1,950 TIME 10 secs

- #6 OPEN PIPE RAMS TO SIMULATE BLIND RAMS / RECORD TIME & PRESSURE.

INTIAL PSI 1,950 FINAL PSI 1,450 TIME 35 secs

- #7 CLOSE HCR (if applicable) / RECORD TIME & PRESSURE.

HCR INTIAL PSI 1,450 FINAL PSI 1,350 TIME 6 secs

- #8 ON THREE RAM STACK CLOSE BOTTOM PIPE RAM / RECORD TIME & PRESSURE.

PIPE RAMS INTIAL PSI 1,350 FINAL PSI 1,300 TIME 7 secs

- #9 WHEN DONE WITH RECORDED TIMES & PRESSURES THERE SHOULD BE
 AT LEAST 200 PSI OVER PRECHARGE IN THE ACCUMLATOR (1200 PSI)

- #10 OPEN ANNULAR

NITROGEN BOTTLES / BLEED OFF TEST

- #1 FINISH BLEEDING OFF BOTTLES INTO ACCUMLATOR TANK/RESERVOIR.
 #2 WATCH & RECORD WHERE PRESSURE DROPS (accumulator psi)

PRESSURE DROP 960 PSI


- #3 ACCUMULATOR PSI SHOULD DROP AT 1100 PSI TO 950 PSI

2 MINUTE TIME TEST / ACCUMULATOR PUMPS

- #1 SHUT VALVES TO NITROGEN BOTTLES.
 #2 PLACE HCR IN THE OPEN POSITION. (if applicable)
 #3 PLACE ANNULAR IN THE CLOSE POSITION.
 #4 TURN ON PUMPS & RECORD TIME TO PRESSURE UP MANIFOLD ON
 ACCUMULATOR TO ATLEAST 200PSI OVER PRECHARGE. WITHIN 2 MIN. OR LESS.

RECORDED TIME 2 MINUTE 10 SEC.

- #5 OPEN VALVES TO NITROGEN BOTTLES & PRESSURE THE ACCUMULATOR BACK
 TO SHUT OFF POINT. THEN OPEN ALL PIPE RAMS & ANNULAR BEFORE PULLING
 PLUG AND DRILL PIPE OUT OF BOP.



TESTED BY:

DOUBLE JACK TESTING
& SERVICES, INC.

SHOSHONI
(307) 876-2308

EVANSTON
(307) 789-9213


VERNAL
(801) 781-0448

CASPER
(307) 265-3678

MICHIGAN
(517) 773-4800

Noble
Unit #166 2-8-05
GC GC-15430

PRINTED
IN
U.S.A.



TESTED BY:

DOUBLE JACK TESTING
& SERVICES, INC.

SHOSHONI
(307) 876-2308

EVANSTON
(307) 789-9213

VERNAL
(801) 781-0448

CASPER
(307) 265-3678


MICHIGAN
(517) 773-4800

Noble

Unit #166 2-9-05

GC GC-15430

PRINTED
U.S.A.



TESTED BY:

DOUBLE JACK TESTING
& SERVICES, INC.

SHOSHONI
(307) 876-2308

EVANSTON
(307) 789-9213

VERNAL
(801) 781-0448

CASPER
(307) 265-3678

MICHIGAN


(517) 773-4800


Noble 8-10 V.A. #166


2-9-05 Antelope

GC GC-15430

PRINTED
U.S.A.







STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

009

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
2. NAME OF OPERATOR: Noble Energy, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 100 Glenborough CITY Houston STATE TX ZIP 77067		7. UNIT OR CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL		8. WELL NAME and NUMBER: Antelope Hollow State 32-20
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S		9. API NUMBER: 43-009-30065
STATE: UTAH		10. FIELD AND POOL, OR WILDCAT: Wildcat

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Weekly Progress Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

02/07/2005 - Cmt. 13 3/8" csg. w/910 sx premlite. Made rough cut on 20" & 13 3/8". Weld on SOW head w/ base plate. Test.
02/08/2005 - Stack & NU BOPE. Test.
02/09/2005 - PU & NU Riser & rotating head. PU new bit.
02/10/2005 - Wash & tag cmt @ 1853'. Drill cmt. Drill to 2295'.
02/11/2005 - Drill to 3100'.
02/12/2005 - Drill to 3564'.
02/13/2005 - Drill to 3902'.

NAME (PLEASE PRINT) Patricia Jaenecke	TITLE Sr. Regulatory Specialist
SIGNATURE <i>Patricia Jaenecke</i>	DATE 2/14/2005

(This space for State use only)

RECEIVED
FEB 18 2005

cc
3/15/05
010

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

ML-47543

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

N/A

7. UNIT or CA AGREEMENT NAME:

N/A

1. TYPE OF WELL

OIL WELL ☒

GAS WELL ☐

OTHER ☐

2. NAME OF OPERATOR:

Noble Energy, Inc.

3. ADDRESS OF OPERATOR:

100 Glenborough

CITY

Houston

STATE

TX

ZIP

77067

PHONE NUMBER:

(281) 874-6765

8. WELL NAME and NUMBER:

Antelope Hollow State 32-20

9. API NUMBER:

009-30065

10. FIELD AND POOL, OR WILDCAT:

Wildcat

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL

COUNTY: Daggett

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will start:

☒ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of work completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☒ OTHER: Weekly Progress Report

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

02/14/2005 - Drill from 3902' to 4357'. Service Rig.

02/15/2005 - Drill to 4390'. Pumped Hi-Vis sweep. Wash & ream to btm. Drill to 4561'.

02/16/2005 - Drill to 4613'. Service rig. Drill to 4899'. Ran survey. Drill to 4920'.

02/17/2005 - Drill to 5285'.

02/18/2005 - Drill to 5624'.

02/19/2005 - Drill to 5912'. POOH.

02/20/2005 - PU new 12 1/4" PDC bit & motor. Wash & ream. Drill to 5919'.

02/21/2005 - Drill to 6445'.

NAME (PLEASE PRINT)

Patricia Jaenecke

TITLE

Sr. Regulatory Specialist

SIGNATURE

DATE

2/22/2005

(This space for State use only)

RECEIVED

FEB 25 2005

DIV. OF OIL, GAS & MINING

011
3/18/05

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

5. LEASE DESIGNATION AND SERIAL NUMBER:

ML-47543

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

N/A

7. UNIT or CA AGREEMENT NAME:

N/A

8. WELL NAME and NUMBER:

Antelope Hollow State 32-20

9. API NUMBER:

43-009-30065

10. FIELD AND POOL, OR WILDCAT:

Wildcat

1. TYPE OF WELL

OIL WELL ☒

GAS WELL ☐

OTHER ☐

2. NAME OF OPERATOR:

Noble Energy, Inc.

3. ADDRESS OF OPERATOR:

100 Glenborough

CITY

Houston

STATE

TX

ZIP

77067

PHONE NUMBER:

(281) 874-6765

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL

COUNTY: Daggett

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will start:

☒ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of work completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☒ OTHER: Weekly Progress Report

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

02/22/2005 - Drill from 6445' to 6980'. Circ & survey. Service Rig.

02/23/2005 - Drill to 7314'. Service Rig.

02/24/2005 - Drill to 7341'. POOH for bit. Drill to 7346'.

02/25/2005 - Drill to 7560'.

02/26/2005 - Drill to 7753'.

02/27/2005 - Drill to 7941'.

NAME (PLEASE PRINT) Patricia Jaenecke

TITLE Sr. Regulatory Specialist

SIGNATURE

DATE

2/28/2005

(This space for State use only)

RECEIVED

MAR 0 / 2005

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

012

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
2. NAME OF OPERATOR: Noble Energy, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 100 Glenborough CITY Houston STATE TX ZIP 77067		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S		8. WELL NAME and NUMBER: Antelope Hollow State 32-20
PHONE NUMBER: (281) 874-6765		9. API NUMBER: 43 009-30065
		10. FIELD AND POOL, OR WILDCAT: Wildcat
		COUNTY: Daggett
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Weekly Progress Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

02/28/2005 - Drill from 7941' to 7967'. POOH.Service Rig. TIH to 7870'. Wash & ream to TD. possible plugged jet.
03/01/2005 - Clean out hole. Pump slug. PU bit #7 and drill to 8048'.
03/02/2005 - Drill to 8303'. Bit stuck when PU to make connection.
03/03/2005 - Jar on stuck hit. Bit free. POOH. PU bit #8 & RIH.
03/04/2005 - RIH to 1900'. Rig Service. Drill to 8556'.
03/05/2005 - Drill to 8817'. Survey @8635'. Drill to 8857'.
03/06/2005 - Drill to 8995'.

NAME (PLEASE PRINT) Patricia Jaenecke	TITLE Sr. Regulatory Specialist
SIGNATURE 	DATE 03/07/05

(This space for State use only)

RECEIVED

MAR 11 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

013

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
2. NAME OF OPERATOR: Noble Energy, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 100 Glenborough CITY Houston STATE TX ZIP 77067		7. UNIT or CA AGREEMENT NAME: N/A
PHONE NUMBER: (281) 874-6765		8. WELL NAME and NUMBER: Antelope Hollow State 32-20
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S		9. API NUMBER: 43-009-30065
		10. FIELD AND POOL, OR WILDCAT: Wildcat
		COUNTY: Daggett
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Weekly Progress Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

03/07/2005 - Drill to 9006'. POOH for bit. Wash & ream to 9006'. Drill to 9010'.
03/08/2005 - Drill to 9144'.
03/09/2005 - Drill to 9167'. Drill string plugged. Determined float in upside-down. POOH to correct float problem.
03/10/2005 - Wash & ream 57' to bottom. Drill to 9254'.
03/11/2005 - Drill to 9292'. Rig service. Drill to 9495'.
03/12/2005 - Drill to 9622'.
03/13/2005 - Drill to 9623'. RIH w/bit. Wash & ream to 9623'. Drill to 9665'.

NAME (PLEASE PRINT) Patricia Jaenecke

TITLE Sr. Regulatory Specialist

SIGNATURE

DATE

3/14/2005

(This space for State use only)

RECEIVED
MAR 21 2005

014

DOUBLE JACK TESTING & SERVICES/IPS
Phone (307) 789-9213

4300930065

B.O.P TEST REPORT

RECEIVED

MAR 28 2005

B.O.P. TEST PERFORMED ON (DATE) 3/20/05

DIV OF OIL, GAS & MINING

OIL COMPANY NOBLE

WELL NAME & NUMBER ANTELOPE HOLLOW

SECTION 20

TOWNSHIP 3 N

RANGE 19 E

COUNTY & STATE DAGGET, UT

DRILLING CONTRACTOR UNIT 166

OIL COMPANY SITE REPRESENTATIVE HOWELL

RIG TOOL PUSHER _____

TESTED OUT OF Evanston, Wyoming

NOTIFIED PRIOR TO TEST _____

COPIES OF THIS TEST REPORT SENT TO: Utah Oil & Gas Commission

BLM - Salt Lake City, Utah

ORIGINAL CHART & TEST REPORT ON FILE AT:

DOUBLE JACK TESTING & SERVICES, INC.
PO BOX 2097
EVANSTON, WY 82930

TESTED BY: Mike Fisher

IPS / dba Double Jack Testing



FIELD TICKET

22195

Accounting Office:

PO Drawer 2080 • Riverton, WY 82501 • (307) 857-0076

Field Operations:

Riverton, WY (307) 857-0077
 Evanston, WY (307) 789-9213
 Rock Springs, WY (307) 382-4020
 Big Piney, WY (307) 276-5265
 Vernal, UT (435) 781-0448

DATE 3-20-05

☒ OPERATOR Noble

☐ CONTRACTOR Unit 166

WELL NAME Antelope Hollow state #32

COUNTY

Dagget

STATE

ut.

SECTION

20

TOWNSHIP

3N

RANGE

19E

Items Tested:

	LOW TEST PSI	TIME HELD MINUTES	HIGHEST PSI	TIME HELD MINUTES	
Top Pipe Rams	250	5	10,000	10	Closing Unit PSI
Bottom Pipe Rams	250	5	10,000	10	Closing Time of Rams
Blind Rams	250	5	10,000	10	Closing Time of Annular
Annular B.O.P.	250	5	3500	10	Closed Casing Head Valve <i>yes</i>
Choke Manifold	250	5	10,000	10	Set Wear Sleeve <i>NO</i>
Choke Line	250	5	10,000	10	
Kill Line	250	5	10,000	10	
Super Choke			10,000	2	
Upper Kelly	250	5	10,000	10	
Lower Kelly	250	5	10,000	10	
Floor Valve	250	5	10,000	10	
Dart Valve	250	5	10,000	10	
Casing			5,700	30	

COMMENTS

ADDITIONAL TESTS & COMMENTS

DRILLING ☒

COMPLETION ☐

WELL NAME & NO. Antelope Hollow state #32-20
 ACTG CODE 24-01
 DOLLAR TOTAL BEING APPROVED \$2884.00
 1ST LEVEL APPROVAL [Signature] DATE 20 Mar 05
 2ND LEVEL APPROVAL [Signature]
 TESTED Back to Pumps to 5000psi. 10 min
 TESTED casing to 5700psi. 30 min

QUANTITY	RATES	TEST PLUG	CHARGES
1 unit	UNIT RATES	TOP SUB. use thiers	
6 hrs	ADDITIONAL	KELLY SUB. 4 1/2 IF	55.00
140 miles	NO RACE	X-OVER SUB. 4 1/2 IF	55.00
193	ANTI FREEZE	OTHER	
		10,000psi	
		Test first 7hrs on Location	1500.00
		Test first 7hrs @ 85 hr	5100.00
		Large Round Trip out of Evanston, WY	3780.00
		50/50 Pre-mix @ \$2 per gallon	3860.00
		OTHER	

PURCHASE ORDER #

NO ACCIDENTS

Mike Fisher

SUBTOTAL 2884.00

TESTED BY

TAX

COMPANY REPRESENTATIVE

DOUBLE JACK TESTING UNIT NUMBER

TOTAL

NOTICE TO ALL CUSTOMERS

If this account shall not be paid when due and it is placed with an attorney for collection, or if suit be instituted for collection, the undersigned agree(s) to pay in either case, reasonable expense of collection including attorney's fees and court cost in compliance with TRUTH IN LENDING AND THE UNIFORM CONSUMER CREDIT CODE, the following information disclosure, under the terms of our regular accounts, all amounts for service due and payable within THIRTY (30) DAYS from the receipt of an invoice for such services. A LATE CHARGE will be assessed when accounts are not paid when due. THE LATE CHARGE is computed by a "periodic rate" 1-3/4% PER MONTH which is an ANNUAL PERCENTAGE RATE OF 21% to the previous balance in the account on the billing date. No further credit can be extended on unpaid delinquent accounts until the delinquent account is paid in full. The contractor will not be held liable for damages caused by acts of God, or unforeseen circumstances that could not be reasonably anticipated in performing the work done as set forth above.

DOUBLE JACK TESTING & SERVICES/IPS

[illegible]

IPS / Double Jack Testing

Accumulator Function Tests

3-20-02
Noble
unit 166
Antelope Hollow state
#32

#1 RECORD INITIAL ACCUMULATOR PRESSURE 3000psi

#2 WITH DRILL PIPE & TEST PLUG INSTALLED IN WELL HEAD.

#3 PLACE ALL FUNCTIONING ACCUMULATOR VALVES IN OPEN POSITION
ALLOW ACCUMULATOR TO PRESSURE UP BEFORE SHUTTING OFF ALL PUMPS

#4 CLOSE ANNULAR / RECORD TIME & PRESSURE.

ANNULAR INTIAL PSI 3000psi FINAL PSI 2000 TIME _____

#5 CLOSE PIPE RAMS / RECORD TIME & PRESSURE.

PIPE RAMS INTIAL PSI 2000 FINAL PSI 1750 TIME _____

#6 OPEN PIPE RAMS TO SIMULATE BLIND RAMS / RECORD TIME & PRESSURE.

INTIAL PSI 1750 FINAL PSI 1600 TIME _____

#7 CLOSE HCR (if applicable) / RECORD TIME & PRESSURE.

HCR INTIAL PSI 1600 FINAL PSI 1600 TIME _____

#8 ON THREE RAM STACK CLOSE BOTTOM PIPE RAM / RECORD TIME & PRESSURE.

PIPE RAMS INTIAL PSI 1600 FINAL PSI 1450 TIME _____

#9 IF YOU HAVE A 3 RAM STACK OPEN THE ANNULAR TO ACHIEVE THE 50+% SAFETY
FACTOR FOR 5M AND GREATER SYSTEMS.

#10 WHEN DONE WITH RECORDED TIMES & PRESSURES THERE SHOULD BE
AT LEAST 200 PSI OVER PRECHARGE IN THE ACCUMLATOR (1200 PSI)

#11 OPEN ANNULAR

NITROGEN BOTTLES / BLEED OFF TEST

#1 FINISH BLEEDING OFF BOTTLES INTO ACCUMLATOR TANK/RESERVOIR.

#2 WATCH & RECORD WHERE PRESSURE DROPS (accumulator psi)

PRESSURE DROP 950 PSI

#3 ACCUMULATOR PSI SHOULD DROP AT 1100 PSI TO 950 PSI

2 MINUTE TIME TEST / ACCUMULATOR PUMPS

#1 SHUT VALVES TO NITROGEN BOTTLES.

#2 PLACE HCR IN THE OPEN POSITION. (if applicable)

#3 PLACE ANNULAR IN THE CLOSE POSITION.


#4 TURN ON PUMPS & RECORD TIME TO PRESSURE UP MANIFOLD ON
ACCUMULATOR TO ATLEAST 200PSI OVER PRECHARGE. WITHIN 2 MIN. OR LESS.

RECORDED TIME 2 MINUTE 12 SEC.

#5 OPEN VALVES TO NITROGEN BOTTLES & PRESSURE THE ACCUMULATOR BACK
TO SHUT OFF POINT. THEN OPEN ALL PIPE RAMS & ANNULAR BEFORE PULLING
PLUG AND DRILL PIPE OUT OF BOP.

10000-15000-20000 PSI

Noble
Unit 166
Antelope Hollow State #32
3-20-05



DOUBLE JACK TESTING

TESTED BY

IPS/
DOUBLE JACK TESTING


3-20-05
DATE


76 min

Antelope Hollow Shale
unit 166

Noble

GC GC-15430
(REV 01)






TESTED BY
IPS/
DOUBLE JACK TESTING

3-20-05
DATE

76 min

Antelope Hollow State
Unit 166 #32
NOLIC

GC GC-15430
(REV 01)



TESTED BY
IPS/
DOUBLE JACK TESTING

3-20-05 96min
DATE

Antelope Hollow State 32

unit 166

Noble

GC GC-15430
(REV 01)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

015

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
2. NAME OF OPERATOR: Noble Energy, Inc.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 100 Glenborough CITY Houston STATE TX ZIP 77067	7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S	8. WELL NAME and NUMBER: Antelope Hollow State 32-20
PHONE NUMBER: (281) 874-6765	9. API NUMBER: 43-009-30065
	10. FIELD AND POOL, OR WILDCAT: Wildcat
	COUNTY: Daggett
	STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Weekly Progress Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

03/14/2005 - Rig Repair. Drill to 9,830'.
03/15/2005 - Drill to 9,964'.
03/16/2005 - Drill to 9,966'. Wiper trip. RU Halliburton to run triple-combo log.
03/17/2005 - RIH w/sonic-dip meter and log. POOH.
03/18/2005 - RU Frank's Westates casing crew and run 9 5/8" csg.
03/19/2005 - Continue running csg. RD Franks'. RU BJ and cmt csg.
03/20/2005 - Cleaning mud tanks. Test BOPE. Test csg - test witnessed by Chris Kierst w/UOGC.
03/21/2005 - RIH w/open-ended. POOH. Installing DP rubbers on every-other joint of DP.
03/22/2005 - Drilling cmt in float joints.
03/23/2005 - Circ. Drill cmt from 9950' thru shoe. Drill to 10,148'.
03/24/2005 - Drill to 10,335'.
03/25/2005 - Drill to 10,581'.
03/26/2005 - Drill to 10,803'.
03/27/2005 - Drill to 10,830'. POOH w/ bit #12, PU bit #13.
03/28/2005 - Drill to 10,895' Service rig.

RECEIVED

APR 01 2005

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Patricia Jaenecke	TITLE Sr. Regulatory Specialist
SIGNATURE 	DATE 3/28/2005

(This space for State use only)

016

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
2. NAME OF OPERATOR: Noble Energy, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 100 Glenborough CITY Houston STATE TX ZIP 77067		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL		8. WELL NAME and NUMBER: Antelope Hollow State 32-20
5. PHONE NUMBER: (281) 874-6765		9. API NUMBER: 43-009-30065
6. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S		10. FIELD AND POOL, OR WILDCAT: Wildcat
7. COUNTY: Daggett		8. STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Weekly Progress Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

04/18/2005 - Drill to 13,442'.
 04/19/2005 - Drill to 13,595'.
 04/20/2005 - Drill to 13,732'.
 04/21/2005 - Drill to 13,900'. Service rig.
 04/22/2005 - Drill to 13,915'. Wiper trip. Pump Hi-Vis sweep. POOH to log. RU Halco, running Triple Combo.
 04/23/2005 - Ran velocity survey tools in hole, began survey.
 04/24/2005 - Ran check-shot seismic survey. RD Halliburton. RU double Jack Testers and test BOPE. RIH w/bit.

NAME (PLEASE PRINT) Patricia Jaenecke	TITLE Sr. Regulatory Specialist
SIGNATURE <i>Patricia Jaenecke</i>	DATE 4/25/2005

(This space for State use only)

RECEIVED
APR 28 2005
DIV. OF OIL, GAS & MINING

017

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
2. NAME OF OPERATOR: Noble Energy, Inc		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 100 Glenborough Drive CITY Houston STATE TX ZIP 77067		7. UNIT or CO-AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844 FNL & 2046 FEL of Section 20		8. WELL NAME and NUMBER: Antelope Hollow State 32-20
9. PHONE NUMBER: (281) 872-3100		9. API NUMBER: 4300930065
10. FIELD AND POOL OR WILDCAT: Wildcat		11. COUNTY: Daggett
12. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S		13. STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 4/26/2005	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

See attached procedure and well bore diagram.

RECEIVED

APR 26 2005

DIV. OF OIL, GAS & MINING

COPY SENT TO OPERATOR
Date: 4-27-05
Initials: CHD

NAME (PLEASE PRINT) James M. Stringfield

TITLE Drilling Consultant

SIGNATURE

James M. Stringfield

DATE

4/26/2005

(This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

(See instructions on Reverse Side)

DATE: 4/26/05

BY: [Signature]

* See conditions of Approval (Attached)

Plugging and Abandonment Procedure
Antelope Hollow State No. 32-20
Daggett County, Utah

Procedure:

1. Trip out of hole and lay down jars, drill collars, shock sub, motor and bit.
2. Trip in hole with cement retainer on DP and set at 9800' +/- . Pressure test annulus to 1000 psi. Establish injection down drill pipe.
3. Pull stinger out of retainer and pressure test casing and retainer to 1000 psi.
4. Mix sufficient cement to fill casing and open hole from 9600' to 10067' (100' in open hole with 50% excess plus 167' in casing below retainer plus 200' on top of the retainer in the casing).
5. Displace cement to the stinger with oil base mud and spacer. Sting into retainer and displace sufficient cement to fill from the retainer to 10067' while monitoring annulus for communication.
6. Pull out of retainer and spot remainder of the cement (sufficient to fill casing from the retainer up to 9600') on top of the retainer.
7. Pull up above the cement plug and reverse out. Wait on cement. Test casing and cement plug to 1000 psi.
8. Displace oil base mud in casing with 9.0 ppg +/- mud from the reserve pit. Return recovered oil base mud to Baroid for credit.
9. Trip out laying down drill pipe to 2100'. Spot a 200' balanced cement plug from 2100' to 1900'.
10. Trip out laying down drill pipe to 200' below ground level.
11. Spot a cement plug in the 9 5/8" casing from 200' below ground level to surface. Lay down remaining drill pipe.
12. Cut off casing strings 3' below ground level.
13. If there is no cement between the 9 5/8" and 13 3/8" casing run 1" tubing to 100' and spot cement from 100' to surface in the 9 5/8" x 13 3/8" annulus.
14. Install state approved monument. Monument must show well number, location and name of the lease. The monument will consist of a length of pipe not less than 4" in diameter and not less than 10' in length, of which 4' must be above the ground level and the remainder securely embedded in cement. The top of the pipe must be permanently sealed.
15. Clean, rig down and move out drilling rig.
16. Develop location restoration plan.



DRILLING WELL PLAN

Antelope Hollow State 32-20

Section 20-T3N-R19E

Daggett County, Utah

PROJECT DESCRIPTION: Plug and abandon well,

WELL PLAN

HOLE	CASING	GEOLOGY	MD/TVD	Elevation - 7010' KB	MUD	CEMENT	DIRECTION	LOGS
Pre-set	20"		100' MD 100' TVD		Water Base			None
17 1/2"	13 3/8" 61 ppf J55 BTC Pc=1540# Pb=3090#		1947' MD 1947' TVD		6.9 ppq Water Base		SBHT 90°F	None
12 1/4"	9 5/8" 53.5 ppf P110 LTC Pc=7950# Pb=10900#	Wasatch	2800' +/-					
8 1/2"		FIT 12.5 ppq Lance Ericson Rock Springs Blair Hillard Actual TD	9967' MD 9967' TVD 10323' 11202' 12073' 13189' 13838' 14300'		9.0 ppq Oil Base Mud 8.9 ppq		SBHT 170°F	
			18250' MD 18250' TVD	JMS	Planned TD		SBHT 253°F	



DRILLING WELL PLAN










Antelope Hollow State 32-20

Section 20-T3N-R19E

Daggett County, Utah

PROJECT DESCRIPTION: Plug and abandon well.

WELL PLAN

HOLE	CASING	GEOLOGY	MD/TVD	Elevation - 7010' KB	MUD	CEMENT	DIRECTION	LOGS
Pre-set	20"		100' MD 100' TVD			BJ cemented w/ 910 sks Premium Lite		None
17 1/2"	13 3/8" 61 ppf J55 BTC Pc=1540# Pb=3090#		1947' MD 1947' TVD		BOC 200'	BJ cemented w/ 910 sks Premium Lite + 655 sks Class G Circ to surface		None
			2800'		TOC 1900'		SBHT 90°F	
12 1/4"	9 5/8" 53.5 ppf P110 LTC Pc=7950# Pb=10900#	Wasatch	9967' MD 9967' TVD		BOC 2100'	BJ cemented w/ 1810 sks Premium Lite + 840 sks Class G - Designed TOC 2800'		
					TOC 9600'			
					Retainer at 9800'			
							SBHT 170°F	
8 1/2"		FIT 12.5 ppg	10323'		BOC 10067'			
		Lance	11202'					
		Ericson	12073'					
		Rock Springs	13189'					
		Blair	13838'					
		Hilliard	14300'					
		Actual TD						
			18250' MD 18250' TVD	JMS	Planned TD		SBHT 253°F	



State of Utah

Department of Natural Resources

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas & Mining

MARY ANN WRIGHT
Acting Division Director

JON M. HUNTSMAN, JR.
Governor


GARY R. HERBERT
Lieutenant Governor

CONDITIONS OF APPROVAL TO PLUG AND ABANDON WELL

Well Name and Number: Antelope Hollow State 32-20
API Number: 43-009-30065
Operator: Noble Energy, Inc.
Reference Document: Original Sundry Notice dated April 26, 2005,
received by DOGM on April 26, 2005

Approval Conditions:

1. Notify the Division at least 24 hours prior to conducting abandonment operations. Please call Dan Jarvis at 801-538-5338.
2. Surface reclamation shall be done in accordance with R649-3-34 – Well Site Restoration. Evidence of compliance with this rule should be supplied to the Division upon completion of reclamation.
3. All requirements in the Oil and Gas Conservation General Rule R649-3-24 shall apply.
4. If there are any changes to the plugging procedure or the wellbore configuration, notify Dustin Doucet at 801-538-5281 (office) or (801) 733-0983 (home) prior to continuing with the procedure.
5. All other requirements for notice and reporting in the Oil and Gas Conservation General Rules shall apply.


Dustin K. Doucet
Petroleum Engineer

April 26, 2005

Date



DRILLING WELL PLAN

Antelope Hollow State 32-20

Section 20-T3N-R19E

Daggett County, Utah

PROJECT DESCRIPTION: Plug and abandon well.

WELL PLAN

HOLE	CASING	GEOLOGY	MD/TVD	Elevation - 7010' KB	MUD	CEMENT	DIRECTION	LOGS
Pre-set	20"		100' MD 100' TVD		100' Annulus Water Base	BJ cemented w/ 910 sks Premium Lite + 655 sks Class G Circ to surface	Plug 3 inside 200' = (695x) outside 100'/(1.15)(2865) = 305x None	None
17 1/2"	13 3/8" 61 ppf J55 BTC Pc=1540# Pb=3090#	Annular Capacity 2.865	1947' MD 1947' TVD	1900'	8.9 ppg Water Base	BJ cemented w/ 1810 sks Premium Lite + 840 sks Class G Designed (TOC 2800'	SBHT 90°F Plug 2 200'/(1.15)(2517) = 695x	995x
12 1/4"	9 5/8" 53.5 ppf P110 LTC Pc=7950# Pb=10900#	Wasatch Capacity 2.517 f/cf	2800'+/- 2100'		200' plug TOC @ 9600' Circ @ 9800'	BJ cemented w/ 1810 sks Premium Lite + 840 sks Class G Designed (TOC 2800'	SBHT 170°F	
8 1/2"		FIT 12.5 ppg Lance Ericson Rock Springs Blair Hilliard Actual TD	9967' MD 9967' TVD 10323' 11202' 12073' 13189' 13838' 14300'		9.0 ppg Oil Base Mud 10067'	Plug 1 Open hole 100'/(1.15)(1762) = 505x Below 107'/(1.15)(2517) = 585x Above 200'/(1.15)(2517) = 695x	1775x	
		Open hole Capacity $\frac{[(1.2)(8.5)]^2}{143.35} = 0.5674 = 1.762 \text{ f/cf}$	18250' MD 18250' TVD	JMS	Planned TD	SBHT 253°F		

100 Glenborough
Suite 100
Houston, TX 77067-3610

Tel: 281.872.3100
Fax: 281.872.2556
www.nobleenergyinc.com

Onshore Division

 noble
energy

Fax

Date:

To: DUSTIN DOLCET **From:** MARK STRINGFIELD
Company: UTAH DIVISION OF OIL, GAS AND MINING **Sender's Phone:** 281-874-6780
Receiver's Phone: 801-538-5281 **Sender's Fax:** 281-872-2555
Receiver's Fax: 801-559-3940 **Total No. Pages:** COVER + 4
Subject: SUNDAY NOTICE TO P&A

☐ Urgent ☐ For Review ☐ Please Comment ☐ Please Reply ☐ Please Recycle

Message:

RECEIVED
APR 26 2005
DIV. OF OIL, GAS & MINING

018

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
2. NAME OF OPERATOR: Noble Energy, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 100 Glenborough CITY Houston STATE TX ZIP 77067		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S		8. WELL NAME and NUMBER: Antelope Hollow State 32-20
PHONE NUMBER: (281) 874-6765		9. API NUMBER: 009-30065
COUNTY: Daggett		10. FIELD AND POOL, OR WILDCAT: Wildcat
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Weekly Progress Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

03/29/2005 - Drill to 11,224
 03/30/2005 - Drill to 11,517'. POOH
 03/31/2005 - POOH for bit trip. Wash & ream to btm. Drill to 11,562'.
 04/01/2005 - Drill to 11,697'
 04/02/2005 - Drill to 11,806'.
 04/03/2005 - Drill to 11,898'. POOH for bit trip. Service rig. Drill to 11,984'.
 04/04/2005 - Drill to 12,183'.
 04/05/2005 - Drill to 12,190'. POOH for bit.
 04/06/2005 - Ream hole 59 12,190'. Drill to 12,310'.
 04/07/2005 - Drill to 12,476'.
 04/08/2005 - Drill to 12,633'. Rig Service.
 04/09/2005 - Drill to 12,700'. POOH for bit.
 04/10/2005 - Rig Service. Wash & ream to 12,700'. Drill to 12,785'.

RECEIVED

APR 18 2005

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Patricia Jaenecke TITLE Sr. Regulatory Specialist
 SIGNATURE *Patricia Jaenecke* DATE 4/11/2005

(This space for State use only)

OC
4/19/05
019

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543
2. NAME OF OPERATOR: Noble Energy, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 100 Glenborough Cty Houston STATE TX ZIP 77067		7. UNIT or CA AGREEMENT NAME: N/A
PHONE NUMBER: (281) 874-6765		8. WELL NAME and NUMBER: Antelope Hollow State 32-20
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1844' FNL & 2046' FEL		9. API NUMBER: 009-30065
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S		10. FIELD AND POOL, OR WILDCAT: Wildcat

COUNTY: Daggett
STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Weekly Progress Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

04/11/2005 - Drill to 12,920'.
04/12/2005 - Drill to 12,089'.
04/13/2005 - Drill to 13,250'.
04/14/2005 - Trip for bit. Reaming tight hole.
04/15/2005 - Wash & ream to 13,254'.
04/16/2005 - Drill to 13,300'. POOH for new bit.
04/17/2005 - Wash & ream hole to 12,400'.

RECEIVED
APR 25 2005
DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Patricia Jaenecke	TITLE Sr. Regulatory Specialist
SIGNATURE <i>Patricia Jaenecke</i>	DATE 4/18/2005

(This space for State use only)

4300930065

DOUBLE JACK TESTING & SERVICES/IPS
Phone (307) 789-9213

020

B.O.P TEST REPORT

B.O.P. TEST PERFORMED ON (DATE) 4/24/05

OIL COMPANY Noble Energy

WELL NAME & NUMBER Antelope Hollow State # 32

SECTION 20

TOWNSHIP 3 N

RANGE 19 E

COUNTY & STATE Dagget

DRILLING CONTRACTOR Unit 166

OIL COMPANY SITE REPRESENTATIVE J. Howell

RIG TOOL PUSHER _____

TESTED OUT OF Evanston, Wyoming

NOTIFIED PRIOR TO TEST _____

COPIES OF THIS TEST REPORT SENT TO: Utah Oil & Gas Commission

BLM- Resource Area

ORIGINAL CHART & TEST REPORT ON FILE AT:

DOUBLE JACK TESTING & SERVICES, INC.
PO BOX 2097
EVANSTON, WY 82930

TESTED BY: John McWhorter

RECEIVED

MAY 09 2005

DIV. OF OIL, GAS & MINING

Double Jack Testing & Services Inc.

FIELD TICKET

No 20741

Accounting Office: P.O. Box 516 Shoshoni, WY 82649 • (307) 876-9390

Field Operations: Shoshoni, WY (307) 876-9390
 Evanston, WY (307) 789-9213
 Rock Springs, WY (307) 382-4020
 Big Piney, WY (307) 276-5265
 Vernal, UT (435) 781-0448

DATE 4-24-05
☒ OPERATOR Noble Energy
☐ CONTRACTOR UNIT 166
 WELL NAME ANTELOPE HOLLAND STATE #32

COUNTY DAGUERRE STATE UTAH SECTION 20 TOWNSHIP 3N RANGE 19E

Items Tested:	LOW TEST PSI	TIME HELD MINUTES	HIGHEST PSI	TIME HELD MINUTES	
Top Pipe Rams	250	5M	10,000	10M	Closing Unit PSI
Bottom Pipe Rams	250	5	10,000	10	Closing Time of Rams
Blind Rams	250	5	10,000	10	Closing Time of Annular
Annular B.O.P.	250	5	3500	10	Closed Casing Head Valve <input checked="" type="checkbox"/>
Choke Manifold	250	5	10,000	10	Set Wear Sleeve
Choke Line	250	5	10,000	10	
Kill Line	250	5	10,000	10	
Super Choke	250	5	10,000	10	
Upper Kelly	250	5	10,000	10	
Lower Kelly	250	5	10,000	10	
Floor Valve	250	5	10,000	10	
Dart Valve	250	5	10,000	10	
Casing					

ADDITIONAL TESTS ☒ COMMENTS ☒ DRILLING ☒ COMPLETION ☐

WELL NAME: ANTELOPE HOLLAND STATE #32
 AFE NO. 44565
 RIG CODE 34-01
 TEST GLUC 13" C22 X 4'2 IF
 TOP SUB. 4 1/2 IF
 KELLY SUB. 4 1/2 IF
 X-OVER SUB.
 OTHER

COMPANY REP. Jim Holland
 TOOL PUSHER BRENT

QUANTITY	RATES	CHARGES
7 HRS	UNIT RATES <u>Minimum 11:30 am - 6:30 pm 10,000 psi</u>	500 ⁰⁰
3	ADDITIONAL <u>Hours @ 25⁰⁰</u>	255 ⁰⁰
100	MILEAGE <u>Round Trip @ 2⁰⁰</u>	378 ⁰⁰
80	ANTIFREEZE <u>gals 50/50 @ 2⁰⁰</u>	160 ⁰⁰
	OTHER <u></u>	


PURCHASE ORDER # TESTED BY John McWhorter NO ACCIDENTS ☐
 COMPANY REPRESENTATIVE J. Holland DOUBLE JACK TESTING UNIT NUMBER 166 TAX
 SUBTOTAL 2563⁰⁰ TOTAL

NOTICE TO ALL CUSTOMERS

If this account shall not be paid when due and it is placed with an attorney for collection, or if suit be instituted for collection, the undersigned agree(s) to pay in either case, reasonable expense of collection including attorney's fees and court cost in compliance with TRUTH IN LENDING AND THE UNIFORM CONSUMER CREDIT CODE, the following information disclosure, under the terms of our regular accounts, all amounts for service due and payable within THIRTY (30) DAYS from the receipt of an invoice for such services. A LATE CHARGE will be assessed when accounts are not paid when due. THE LATE CHARGE is computed by a "periodic rate" 1-3/4% PER MONTH which is an ANNUAL PERCENTAGE RATE OF 21% to the previous balance in the account on the billing date. No further credit can be extended on unpaid delinquent accounts until the delinquent account is paid in full. The contractor will not be held liable for damages caused by acts of God, or unforeseen circumstances that could not be reasonably anticipated in performing the work done as set forth above.

DOUBLE JACK TESTING & SERVICES/IPS

[illegible]



#7 mud lines from Kelly to Pumps

DOUBLE JACK TESTING

XIOBLE ENERGY
UNIT 106
ARITALOPIE HOLLAND STRIKE # 32
IPS / Double Jack Testing
4/24/05

Accumulator Function Tests

- # 1 RECORD INITIAL ACCUMULATOR PRESSURE 3000
2 WITH DRILL PIPE & TEST PLUG INSTALLED IN WELL HEAD.
3 PLACE ALL FUNCTIONING ACCUMULATOR VALVES IN OPEN POSITION
ALLOW ACCUMULATOR TO PRESSURE UP BEFORE SHUTTING OFF ALL PUMPS
4 CLOSE ANNULAR / RECORD TIME & PRESSURE.

ANNULAR INTIAL PSI 3000 FINAL PSI 1900 TIME 41

- # 5 CLOSE PIPE RAMS / RECORD TIME & PRESSURE.

PIPR RAMS INTIAL PSI 1100 FINAL PSI 1650 TIME 9

- # 6 OPEN PIPE RAMS TO SIMULATE BLIND RAMS / RECORD TIME & PRESSURE.

INTIAL PSI 1650 FINAL PSI 1550 TIME 9

- # 7 CLOSE HCR (if applicable) / RECORD TIME & PRESSURE.

~~HCR~~ Blind Rams INTIAL PSI 1550 FINAL PSI 1450 TIME 9

- # 8 ON THREE RAM STACK CLOSE BOTTOM PIPE RAM / RECORD TIME & PRESSURE.

HCR PIPE RAMS INTIAL PSI 1450 FINAL PSI 1450 TIME 2

- # 9 WHEN DONE WITH RECORDED TIMES & PRESSURES THERE SHOULD BE
AT LEAST 200 PSI OVER PRECHARGE IN THE ACCUMULATOR (1200 PSI)

- # 10 OPEN ANNULAR

NITROGEN BOTTLES / BLEED OFF TEST

- # 1 FINISH BLEEDING OFF BOTTLES INTO ACCUMULATOR TANK/RESERVOIR.
2 WATCH & RECORD WHERE PRESSURE DROPS (accumulator psi)

PRESSURE DROP 900 PSI


- # 3 ACCUMULATOR PSI SHOULD DROP AT 1100 PSI TO 950 PSI


2 MINUTE TIME TEST / ACCUMULATOR PUMPS


- # 1 SHUT VALVES TO NITROGEN BOTTLES.
2 PLACE HCR IN THE OPEN POSITION. (if applicable)
3 PLACE ANNULAR IN THE CLOSE POSITION.
4 TURN ON PUMPS & RECORD TIME TO PRESSURE UP MANIFOLD ON
ACCUMULATOR TO ATLEAST 200PSI OVER PRECHARGE. WITHIN 2 MIN. OR LESS.


RECORDED TIME 1 MINUTE 49 SEC.

- # 5 OPEN VALVES TO NITROGEN BOTTLES & PRESSURE THE ACCUMULATOR BACK
TO SHUT OFF POINT. THEN OPEN ALL PIPE RAMS & ANNULAR BEFORE PULLING
PLUG AND DRILL PIPE OUT OF BOP.









100 Glenborough
Suite 100
Houston, TX 77067-3299

Tel: 281.872.3100
Fax: 281.876.8891
www.nobleenergyinc.com



43-009-30065

Onshore Division

May 18, 2005

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Salt Lake City, Utah 84114-5801

Re: Antelope Hollow State 32-20
Wildcat Field
API 43-009-30065
Daggett, Utah

Gentlemen;

Enclosed please find, in duplicate, the Completion Report (Form 8) and Sundry Notice (Form 9) for the above referenced well, which was plugged and abandoned. Also enclosed are copies of the logs.

If you have any questions or need additional information, please contact me at (281) 874-6765.

Sincerely,

Patricia Jaenecke
Sr. Regulatory Specialist

Enclosures
Antelope Hollow omp

RECEIVED
MAY 2 / 2005
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input type="checkbox"/>	DRY <input checked="" type="checkbox"/>	OTHER <input type="checkbox"/>		
b. TYPE OF WORK:		NEW WELL <input checked="" type="checkbox"/>	HORIZ. LATS. <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	RE-ENTRY <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	OTHER <input type="checkbox"/>
2. NAME OF OPERATOR: Noble Energy, Inc.						5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47543	
3. ADDRESS OF OPERATOR: 100 Glenborough #100 CITY Houston STATE TX ZIP 77067						6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1844 FNL & 2046 FEL of Section 20 AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH:						7. UNIT or CA AGREEMENT NAME	
PHONE NUMBER: (281) 874-6765						8. WELL NAME and NUMBER: Antelope Hollow State 32-30	
10 FIELD AND POOL, OR WILDCAT Wildcat						9. API NUMBER: 4300930065	
11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 20 3N 19E S						12. COUNTY Daggett	
						13. STATE UTAH	

14. DATE SPURRED: 2/2/2005	15. DATE T.D. REACHED: 4/26/2005	16. DATE COMPLETED: 5/1/2005	ABANDONED <input checked="" type="checkbox"/> READY TO PRODUCE <input type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 7093.2
18. TOTAL DEPTH: MD 14,175 TVD 14,175	19. PLUG BACK T.D.: MD 14,175 TVD 14,175	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) Induction-Sonic/dipmeter/acoustic imaging, <i>HRZ, SD/DEM</i>				23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
17 1/2	J-55	61.0	0	1,947		PremLt 1,565	2,832	Cir	0
12 1/4	9.875 P110	53.5	0	9,967		PremLt 2,650	6,668	Cal	0

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL

29. ENCLOSED ATTACHMENTS:

- | | | | |
|--|--|---------------------------------------|---|
| <input checked="" type="checkbox"/> ELECTRICAL/MECHANICAL LOGS | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT | <input type="checkbox"/> DIRECTIONAL SURVEY |
| <input checked="" type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS | <input type="checkbox"/> OTHER: _____ | |

DIV. OF OIL, GAS & MINING

P&A

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				Lance	10323
				Ericson	11202
				Rock Springs	12073
				Blair	13189
				Hilliard	13838

35. ADDITIONAL REMARKS (Include plugging procedure)

RIH w/Baker cmt retainer. Set @ 9810'. RU Halliburton. Mix & spot 210 sx Class "G" cmt. Pump 28.6 bbls below retainer & 14.3 bbls on top. LD DP. Spot cmt plug from 1900'-2100'. RIH to 210'. Pump top plug to surface (70 sx Class "G") Cut off wellhead & weld on plate.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Patricia Jaenecke

TITLE Sr. Regulatory Specialist

SIGNATURE *Patricia Jaenecke*

DATE 5/4/2005

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation

- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Dry Hole</u>			5. LEASE DESIGNATION AND SERIAL NUMBER: <u>ML-47543</u>
2. NAME OF OPERATOR: <u>Noble Energy, Inc.</u>			6. IF INDIAN, ALLOTTEE OR TRIBE NAME: <u>N/A</u>
3. ADDRESS OF OPERATOR: <u>100 Glenborough</u> CITY <u>Houston</u> STATE <u>TX</u> ZIP <u>77067</u>			7. UNIT or CA AGREEMENT NAME: <u>N/A</u>
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>1844' FNL & 2046' FEL</u>			8. WELL NAME and NUMBER: <u>Antelope Hollow State 32-20</u>
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <u>SWNE 20 3N 19E S</u>			9. API NUMBER: <u>009-30065</u>
COUNTY: <u>Daggett</u>			10. FIELD AND POOL, OR WILDCAT: <u>Wildcat</u>
STATE: <u>UTAH</u>			

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

04/27/2005 - RIH w/Baker cement retainer. Set @ 9810'. Tested DP & retainer to 1000 psi. RU Halliburton. Mixed & spotted 210 sx Class "G" + 0.1% HR-5 (43 bbls slurry @ 18.8 ppg, yield 1.15) Pumped 28.6 bbls below retainer & 14.3 bbls on top of retainer. RU Frank's Westates L/D machine & LD 5" DP.

04/28/2005 - RIH w/OEDP to 2100'. RU Halliburton. spotted cement plug from 1900'-2100' (70 sx Class "G" + 2% CACL2 mixed @ 15.8 ppg, 14.3 bbls slurry). Finish LD DP & BHA. RIH to 210'. pumped top plug from 210' to surface (70 sx Class "G" + 2% CACL2, 14.3 bbls Slurry @ 15.8 ppg). RD Halliburton

04/29/2005 - Cut off wellhead

04/30/2005 - RU Halliburton. Ran 1" tubing in 9 5/8" x 13 3/8" annulus to 100'. Mixed & pumped 50 sx Class "G" cmt. Got cement returns to surface. RD Halliburton. Welded plate on top of cut-off 13 3/8" x 9 5/8" csg.

05/01/2005 - Release rig @ 0600.

****The hole was circulated with 662 bbls 8.8# water based mud. Approval for welding the plate on the csg was given by Chris Kierst with the Department of Natural Resources.**

NAME (PLEASE PRINT) <u>Patricia Jaenecke</u>	TITLE <u>Sr. Regulatory Specialist</u>
SIGNATURE	DATE <u>5/4/2005</u>

(This space for State use only)

RECEIVED
MAY 2 / 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 7

REPORT OF WATER ENCOUNTERED DURING DRILLING

Well name and number: Antelope Hollow State 32-20

API number: 009-30065

Well Location: QQ SWNE Section 20 Township 3N Range 19E County Daggett

Well operator: Noble Energy, Inc.

Address: 100 Glenborough, #100

city Houston state TX zip 77067

Phone: (281) 874-6765

Drilling contractor: Unit Drilling Company

Address: 7130 S. Lewis, Ste. 1000

city Tulsa state OK zip 74136

Phone: _____

Water encountered (attach additional pages as needed):

DEPTH		VOLUME (FLOW RATE OR HEAD)	QUALITY (FRESH OR SALTY)
FROM	TO		
20'	20'	Water in Conductor Hole	Fresh

Formation tops: (Top to Bottom)

1	<u>Lance - 10323</u>	2	<u>Ericson - 11202</u>	3	<u>Rock Springs - 12073</u>
4	<u>Blair - 13189</u>	5	<u>Hilliard - 13838</u>	6	_____
7	_____	8	_____	9	_____
10	_____	11	_____	12	_____

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

I hereby certify that this report is true and complete to the best of my knowledge.

NAME (PLEASE PRINT)

Patricia Jaenecke

TITLE

Sr. Regulatory Specialist

SIGNATURE

Patricia Jaenecke

DATE


05/25/2005

RECEIVED

MAY 2 / 2005

4300930065
3N 19E Sec. 20
EARTHWORKS INC.

8 Sunny Terrace
Riverton, WY 82501



Noble Energy, Inc.
Antelope Hollow 32-20

KEN HOSTETTER
307-851-6515 Cell
307-857-4260 Office

DAILY ACTIVITY REPORT

Noble Energy, Inc.

Antelope Hollow 32-20

May 19-05

Thursday

6:48 AM: Arrive on location, have safety meeting.

7:16 AM: Excavator was delivered on location.

8:20 AM: First two pneumatics are on location.

9:00 AM: Start unloading reagent into reserve pit.

11:14 AM: Done unloading first two pneumatics, Third pneumatics arrives on location start unloading reagent into pit.

12:15 PM: Done unloading third truck, start-mixing reagent.

3:30 PM: Done mixing pit, start backfilling.

6:30 PM: Finished backfilling, done for the day.

6:45 PM: Off location.

May 20-05

Friday

7:00 AM: Arrived on location.

7:20 AM: First two pneumatics trucks arrive on location, have safety meeting.

8:00 AM: Start unloading reagent into reserve pit.

10:15 AM: Done unloading first two trucks, third truck arrives, start-unloading reagent.

11:55 AM: Start mixing reagent and sludge together.

3:40 PM: Finished mixing reagent, take composite sample of treated material, start-covering pit.

4:30 PM: Done for the day, off location.

May 23-05

Monday

- 8:00 AM: Arrive on location, have safety meeting.
- 8:10 AM: Start unloading pneumatic trucks into reserve pit.
- 12:15 PM: Done unloading reagent, start mixing reagent and sludge together.
- 2:30 PM: Finished mixing pit, take composite sample of treated material.
- 3:05 PM: Done for the day, off location.

May 24-05

Tuesday

- 8:00 AM: Arrive on location, have safety meeting.
- 8:30 AM: Start unloading pneumatic truck into reserve pit.
- 9:58 AM: Done unloading reagent into pit.
- 10:14 AM: Start mixing reagent into pit.
- 12:00 PM: Finished mixing, take composite sample of treated material.
- 12:31 PM: Start placing cover soil over pit.
- 2:44 PM: Finished cover soil, project finished, off location.

EARTHWORKS INC.

DAILY JOBSITE SAFETY ASSESSMENT FORM (JSA)

Date: <u>5-19-05-5-24-05</u>	Start Time: <u>7.00 Am</u>	Stop Time: <u>5.00 pm</u>
Work Activity (Job): <u>SOLIDIFY RESERVE PIT</u>		Location: <u>Noble Energy Antelope Hollow 32-20</u>

Sequence of Basic Job Steps	Potential Accidents or Hazards	Recommendations to Eliminate or Reduce Potential Hazards
unload reagent	dusty conditions	work upwind-check
	pressure vessel & lines	equipment daily
mix pit	heavy equipment	communication
		know movement of
cover pit	same above	equipment

Site Drawing

↑
N

EXIT

Well Head

Pit

Reserve Pit

Key Information (smoking area, overhead power, hot work zone, valves for lock out tag out, confined space emergency escape)

	Y	N		Y	N
Hot work permits	<input type="checkbox"/>	<input type="checkbox"/>	Confined space	<input type="checkbox"/>	<input type="checkbox"/>
Trenching	<input type="checkbox"/>	<input type="checkbox"/>	Power lines	<input type="checkbox"/>	<input type="checkbox"/>
USA notified	<input type="checkbox"/>	<input type="checkbox"/>	Blue Sky	<input type="checkbox"/>	<input type="checkbox"/>
			Other _____	<input type="checkbox"/>	<input type="checkbox"/>

Safety equipment required to do this job

Hard hat <input checked="" type="checkbox"/>	Exhaust fans	Barricades	Fire extinguisher <input checked="" type="checkbox"/>	date
Safety shoes <input checked="" type="checkbox"/>	Safety helmets <input checked="" type="checkbox"/>	Respirator	SCBA	date
Safety glasses <input checked="" type="checkbox"/>	Face shields	Breathing Air	H2S monitor	date
Gloves <input checked="" type="checkbox"/>	Goggles	Lock out tag out	Tri monitor	date
			First aid kit <input checked="" type="checkbox"/>	date

Supervisor Responsible: <u>Math Diener</u>	Contract or Supervisor: <u>Ken</u>
Signatures: _____	



Earthworks, Inc.
Pre-Testing Results


Operator Noble Energy

Well Antelope Hollow 32-20

TPH 22% Water 62% Solids 16%

All above values are arrived at using a baroid retort distillation unit and represent percentage of volume of sample tested.

Tested by Kenneth Hatette

**CONTI TESTING LABORATORIES, INC.**

P.O. BOX 174 - BETHEL PARK, PA 15102

(412) 833-7766 • Fax (412) 854-0373

contilab@verizon.net

Earthworks Inc
8 Sunny Terrace
Riverton Wyoming 82501
Mr. Ken Hostetter
Office: 307-851-6515
Fax: 307-857-4260
earthworks04@aol.com

7/11/2005


Received: 7/1/2005
Sampled By: client
CTL ID: 94160

Sample ID: Noble Energy Antelope Hollow 32-20

	Results (mg/l)	Method TCLP Extraction	DL
Total Dissolved Solids	3,950	EPA 160.1	10
Total Petroleum Hydrocarbon	2.9	EPA 413.2	0.1

ref: TCLP Extraction Fluid # 2

Approved by: 

**CONTI TESTING LABORATORIES, INC.**

P.O. BOX 174 - BETHEL PARK, PA 15102

(412) 833-7766 • Fax (412) 854-0373

contilab@verizon.net

Earthworks Inc
8 Sunny Terrace
Riverton Wyoming 82501
Mr. Ken Hostetter
Office: 307-851-6515
Fax: 307-857-4260
earthworks04@aol.com

7/11/2005

Received: 7/1/2005
Sampled By: client
CTL ID: 94159

Sample ID: **Noble Energy Antelope Hollow 32-20**

	Results (mg/l)	Method <u>Wyoming Leachate</u>	DL
Total Dissolved Solids	4,860	EPA 160.1	10
Total Petroleum Hydrocarbon	3.2	EPA 413.2	0.1

ref: WYO Leachate

Approved by: *[Signature]*

Earthworks, Inc.
Regulatory Agency Pit Closure Report

1. Report submitted to Utah Oil Gas
2. Content of pit Oil based drill cuttings and sludge
3. Size of pit 3,976 bbls
4. Operator Noble Energy, Inc
5. Closure Contractor Earthworks, Inc.
6. Lease Name & Number Antelope Hollow 32-20
7. Location Sec 20 T3N R19E Dagget Co. Utah
8. Start Date 05-19-05 End Date 05-24-05
9. Treating Materials added LKD, CKD, Portland cement.
10. Was pit Lined YES
11. Pretreatment Analysis (attached)
TPH 22% TDS N/A
12. Post treatment analysis (attached)
Wyoming Leachate testing method
TPH 2.9 < 10mg/L TDS 3,950 < 5000 mg/l
13. Stiffness/Compressive strength test results Ran 627 scraper over pit
14. Type of pit Reserve pit

Signed Kenneth Hattetta Title President Date 07-18-05